

FILE NAME : G:\Projects\ILLINOIS Department of Transportation\16162 - Item 7 - Various Pavement Work Under No. 1 (Route) - US 20 et al. R. 47 & J. 2\AN\Civil\Land Survey\2158783.dwg 6/24/14

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				0004	0021	0021	0021	0021					
				80% FEDERAL	80% FEDERAL	80% FEDERAL	100% VILLAGE OF	80% FEDERAL					
				20% STATE	20% STATE	20% STATE	PINGREE GROVE	20% STATE					
				ROADWAY	TRAFFIC	INTERCONNECT	FIRE PROT. DIST.	LIGHTING					
					SIGNALS		SAFETY (EVP)						
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2									
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1									
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1									
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2	2									
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	616	616									
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	877	877									
60107700	PIPE UNDERDRAINS 6"	FOOT	1,613	1,613									
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	9	9									
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1									
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4									
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	300	300									
63200310	GUARDRAIL REMOVAL	FOOT	450	450									
64300450	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12									

14

USER NAME : shriefer PLOT SCALE : 100,000 1" = 1 mi. PLOT DATE : 6/17/2014	DESIGNED - MTM DRAWN - MTM	REVISIONS REVISIONS REVISIONS	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. : 345	SECTION : 106-5-N-2	COUNTY : KANE	TOTAL SHEET NO. : 147	SHEETS : 8
	CHECKED - BA DATE - 3/31/14	SCALE: N.T.S.			SHEET 5 OF 13 SHEETS STA. TO STA.	CONTRACT NO. 60T09	ILLINOIS FED. AID PROJECT		