

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
				0004	0021	0021	0021	0021
				80% FEDERAL	80% FEDERAL	80% FEDERAL	100% VILLAGE OF	80% FEDERAL
				20% STATE	20% STATE	20% STATE	PINGREE GROVE	20% STATE
			ROADWAY	TRAFFIC	INTERCONNECT	FIRE PROT. DIST.	LIGHTING	
				SIGNALS		SAFETY (EVP)		
67100100	MOBILIZATION	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	90	90				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	19,170	19,170				
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	473	473				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10,587	10,587				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2,207	2,207				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	368	368				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	187	187				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	6,390	6,390				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,588	1,588				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	988	988				
70600270	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, WIDE), TEST LEVEL 3	EACH	6	6				
70600330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	4	4				
△ 72000100	SIGN PANEL - TYPE 1	SO FT	9		9			

△ SPECIALTY ITEM

FILE NAME * #FILE# SMT_PLAN	USER NAME * #USER#	DESIGNED - MTM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RIE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE * #SCALE#	DRAWN - MTM	REVISED -					345	106-S-N-2	KANE	147	9
	PLOT DATE * #DATE#	CHECKED - BA	REVISED -					CONTRACT NO. 60T09				
	DATE - 3/31/14	REVISED -	ILLINOIS FED. AID PROJECT									
					SCALE: N.T.S.	SHEET 6 OF 13 SHEETS	STA.	TO STA.				

11