

FILE NAME : G:\Projects\1311112\Department of Transport\Addition\131112 - Item 7 - Various Materials\Draw No. 11\000010 - 105 28 at IL 47 & IL 72\Draw\Code Sheets\11121218-ah-Sub.dgn
 14

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				0004 80% FEDERAL 20% STATE ROADWAY	0021 80% FEDERAL 20% STATE TRAFFIC SIGNALS	0021 80% FEDERAL 20% STATE INTERCONNECT	0021 100% VILLAGE OF PINGREE GROVE FIRE PROT. DIST. SAFETY (EVP)	0021 80% FEDERAL 20% STATE LIGHTING	
△ 87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	1		1				
△ 87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT.	EACH	2		2				
△ 87702980	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 50 FT.	EACH	1		1				
△ 87702985	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT.	EACH	1		1				
△ 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	20		20				
△ 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4				
△ 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	56		56				
△ 87900205	DRILL EXISTING HEAVY DUTY HANDHOLE	EACH	2			2			
△ 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	1		1				
△ 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	7		7				
△ 88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	3		3				
△ 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1		1				
△ 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	8		8				
△ 88500100	INDUCTIVE LOOP DETECTOR	EACH	10		10				

△ SPECIALTY ITEM

USER NAME : DESIGNED - MTM DRAWN - MTM CHECKED - BA DATE - 3/31/14	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES SCALE: N.T.S. SHEET 10 OF 13 SHEETS STA. TO STA.	F.A.P. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO. 345 106-S-N-2 KANE 147 13 CONTRACT NO. 60T09 ILLINOIS FED. AID PROJECT
--	--	---	---	---