CODE NO.	ITEM	UNIT	TOTAL QUANTITY (URBAN)	CONSTRUCTION CODE: 0004 80% FEDERAL 20% STATE ROADWAY	0021 80% FEDERAL 20% STATE TRAFFIC SIGNALS	0021 80% FEDERAL 20% STATE INTERCONNECT	0021 100% VILLAGE OF PINGREE GROVE FIRE PROT. DIST. SAFETY (EVP)	0021 80% FEDERAL 20% STATE LIGHTING	
~~50200450~~	~~REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS FOR STRUCTURES~~	~~CU YD~~	~~495~~	~~495~~	1				
50200100	STRUCTURE EXCAVATION	CU YD	1119	1119					
50300225	CONCRETE STRUCTURES	CU YD	4.4	4.4					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	207,500	207,500	1				
50300300	PROTECTIVE COAT	SQ YD	15	15					
50800515	BAR SPLICERS	EACH	276	276	1				
51500100	NAME PLATES	EACH	2	2					
54003000	CONCRETE BOX CULVERTS	CU YD	787.7	787.7					
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	58	58					
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	80	80					
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2					
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1					
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	2	2					
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1					
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2					
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1,018	1,018					
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	182	182					

1 Rev. 7-17-14

Rev.

USER NAME = ohrisfish	DESIGNED - MTM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION
	DRAWN - MTM	REVISED -	
PLOT SCALE = 100.0000 ' / in.	CHECKED - BA	REVISED -	
PLOT DATE = 4/1/2014	DATE - 3/31/14	REVISED -	

SHT_PLAN

SUMMARY OF QUANTITIES

SCALE: N.T.S. | SHEET 5 OF 15 SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
345	106-S-N-1	KANE	167	8

CONTRACT NO. 60T10

ILLINOIS FED. AID PROJECT