

CONSTRUCTION CODE					
0004 80% FEDERAL 20% STATE ROADWAY	0021 80% FEDERAL 20% STATE TRAFFIC SIGNALS	0021 80% FEDERAL 20% STATE INTERCONNECT	0021 100% VILLAGE OF PINGREE GROVE FIRE PROT. DIST. SAFETY (EVP)	0021 80% FEDERAL 20% STATE LIGHTING	

URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0004 80% FEDERAL 20% STATE ROADWAY	0021 80% FEDERAL 20% STATE TRAFFIC SIGNALS	0021 80% FEDERAL 20% STATE INTERCONNECT	0021 100% VILLAGE OF PINGREE GROVE FIRE PROT. DIST. SAFETY (EVP)	0021 80% FEDERAL 20% STATE LIGHTING
△ 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	506	506				
△ 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	506	506				
△ 25100135	MULCH, METHOD 4	ACRE	5.40	5.40				
△ 25100630	EROSION CONTROL BLANKET	SQ YD	26,955	26,955				
28000305	TEMPORARY DITCH CHECKS	FOOT	1341	1,341				
28000315	AGGREGATE DITCH CHECKS	TON	5.0	5.0				
28000400	PERIMETER EROSION BARRIER	FOOT	8,688	8,688				
28000510	INLET FILTERS	EACH	67	67				
28001100	TEMPORARY EROSION CONTROL BLANKET	SQ YD	6188	6,188				
28100101	STONE RIPRAP, CLASS A1	SQ YD	160	160				
28100107	STONE RIPRAP, CLASS A4	SQ YD	321	321				
28200200	FILTER FABRIC	SQ YD	592	592				
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	112	112				
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	4,027	4,027				

FILE NAME : G:\p\p\state\ILLINOIS\Department of Transportation\OTIS 102 - Item 7 - Various Venues\Mark Order No. 10 - 100 - 105 - 28 at IL 47 A IL 72\Urban\Road Sheets\102\105-28-102.dwg
 User Name : shafiqah
 DESIGNED - MTM
 DRAWN - MTM
 CHECKED - BA
 DATE - 3/31/14
 PLOT SCALE = 100:2000 1/2"=1'
 PLOT DATE = 4/1/2014

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET 2 OF 15 SHEETS STA. TO STA.

A Specialty Items Rev.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	106-S-N-1	KANE	167	5
CONTRACT NO. 60T10				
ILLINOIS FED. AID PROJECT				