CODE NO.	ITEM	UNIT	TOTAL QUANTITY (URBAN)	CONSTRUCTION CODE: 0004 80% FEDERAL 20% STATE ROADWAY	0021 80% FEDERAL 20% STATE TRAFFIC SIGNALS	0021 80% FEDERAL 20% STATE INTERCONNECT	0021 100% VILLAGE OF PINGREE GROVE FIRE PROT. DIST. SAFETY (EVP)	0021 80% FEDERAL 20% STATE LIGHTING	
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS FOR STRUCTURES	CU YD	495	495					
50200100	STRUCTURE EXCAVATION	CU YD	1119	1119					
50300225	CONCRETE STRUCTURES	CU YD	4.4	4.4					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	141,400	141,400					
50300300	PROTECTIVE COAT	SQ YD	15	15					
50800515	BAR SPLICERS	EACH	250	250					
51500100	NAME PLATES	EACH	2	2					
54003000	CONCRETE BOX CULVERTS	CU YD	787.7	787.7					
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	58	58					
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	80	80					
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2					
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1					
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	2	2					
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1					
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2					
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1,018	1,018					
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	182	182					

Rev.