

FILE NAME: G:\M-0505\VEI BRIS Department of Transportation\111 B2 - Item 7 - Various Various\Work Order No. 18 Item 03 - US 20 at I. 47 R. R. Zschock\Add Sheets\111B2R-001.dgn
 SHEET PLAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				0004	0021	0021	0021	0021	
				80% FEDERAL	80% FEDERAL	80% FEDERAL	100% VILLAGE OF	80% FEDERAL	
				20% STATE	20% STATE	20% STATE	PINGREE GROVE	20% STATE	
				ROADWAY	TRAFFIC	INTERCONNECT	FIRE PROT. DIST.	LIGHTING	
					SIGNALS		SAFETY (EVP)		
550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	455	455					
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	448	448					
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	155	155					
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	731	731					
550A5100	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 30"	FOOT	289	289					
55100200	STORM SEWER REMOVAL 6"	FOOT	30	30					
55100400	STORM SEWER REMOVAL 10"	FOOT	98	98					
55100500	STORM SEWER REMOVAL 12"	FOOT	99	99					
55100700	STORM SEWER REMOVAL 15"	FOOT	239	239					
55100900	STORM SEWER REMOVAL 18"	FOOT	45	45					
55101200	STORM SEWER REMOVAL 24"	FOOT	46	46					
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	16	16					
60107700	PIPE UNDERDRAINS 6"	FOOT	3127	3127					
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	6	6					

URBAN

Rev.

USER NAME: DESIGNED - MTM DRAWN - MTM CHECKED - BA DATE - 3/31/14	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES SCALE: N.T.S. SHEET 6 OF 15 SHEETS STA. TO STA.	F.A.P. RTE. 345 SECTION 106-S-N-1 COUNTY KANE TOTAL SHEETS 167 SHEET NO. 9 CONTRACT NO. 60T10 ILLINOIS FED. AID PROJECT
---	--	---	--	---