

I:\Projects\11511015 - Highway\11511015.dwg - Item 7 - Vertical Curves\Mark - B - 40 - 11511015.dwg - Item 7 - Vertical Curves\Mark - B - 40 - 11511015.dwg
 User: MTM
 Date: 3/31/14
 PLOT DATE: 4/1/2014

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				0004 80% FEDERAL 20% STATE ROADWAY	0021 80% FEDERAL 20% STATE TRAFFIC SIGNALS	0021 80% FEDERAL 20% STATE INTERCONNECT	0021 100% VILLAGE OF PINGREE GROVE FIRE PROT. DIST. SAFETY (EVP)	0021 80% FEDERAL 20% STATE LIGHTING	
△ 72000200	SIGN PANEL - TYPE 2	SQ FT	80.5		80.5				
△ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	619	619					
△ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	24,191	24,191					
△ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2403	2403					
△ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	527	527					
△ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	172	172					
△ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	505	505					
△ 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	58	58					
△ 78200530	BARRIER WALL MARKERS, TYPE C	EACH	85	85					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	442	442					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	490	490					
△ 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1					1	
△ 80400200	ELECTRIC UTILITY SERVICE CONNECTION	LSUM	1					1	
△ 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1				

△ SPECIALTY ITEM

USER NAME = gherafish PLOT SCALE = 1/8" = 1' / 1" / 1" PLOT DATE = 4/1/2014				DESIGNED - MTM DRAWN - MTM CHECKED - BA DATE - 3/31/14				REVISED - REVISED - REVISED - REVISED -				STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES				F.A.P. RTE. 345		SECTION 106-S-N-1		COUNTY KANE		TOTAL SHEETS 167		SHEET NO. 12	
SCALE: N.T.S.		SHEET 9 OF 15 SHEETS		STA.		TO STA.		ILLINOIS FED. AID PROJECT												CONTRACT NO. 60T10									