

C:\Users\mike.norris\Documents\Projects\60110\60110.dwg

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				0004	0021	0021	0021	0021	
				80% FEDERAL	80% FEDERAL	80% FEDERAL	100% VILLAGE OF	80% FEDERAL	
				ROADWAY	TRAFFIC SIGNALS	INTERCONNECT	PINGREE GROVE FIRE PROT. DIST. SAFETY (EVP)	20% STATE	20% STATE
Δ 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	981		981				
Δ 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	3		3				
Δ 87702960	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 46 FT.	EACH	1		1				
Δ 87702980	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 50 FT.	EACH	1		1				
Δ 87702990	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 54 FT.	EACH	1		1				
Δ 87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT.	EACH	1		1				
Δ 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12		12				
Δ 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4				
Δ 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	58		58				
Δ 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	1		1				
Δ 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	7		7				
Δ 88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	3		3				
Δ 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1		1				
Δ 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	8		8				

Δ SPECIALTY ITEM

14

USER NAME = <i>mkreftan</i> PLOT SCALE = 1/8"=1'-0" PLOT DATE = 4/2/2014	DESIGNED - MTM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE. 345 SECTION 106-S-N-I COUNTY KANE CONTRACT NO. 60110	TOTAL SHEETS	SHEET NO.
	DRAWN - MTM	REVISED -		SCALE: N.T.S.	SHEET 12	OF 15 SHEETS	STA.		TO STA.	167
	CHECKED - BA	REVISED -								
	DATE - 3/31/14	REVISED -								

ILLINOIS FED. AID PROJECT