

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				0004 80% FEDERAL 20% STATE ROADWAY	0021 80% FEDERAL 20% STATE TRAFFIC SIGNALS	0021 80% FEDERAL 20% STATE INTERCONNECT	0021 100% VILLAGE OF PINGREE GROVE FIRE PROT. DIST. SAFETY (EVP)	0021 80% FEDERAL 20% STATE LIGHTING	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
Z0054406	ROCK FILL - FOUNDATION	CU YD	475	475					
Z0055905	TEMPORARY CONSTRUCTION FENCE	FOOT	1,990	1,990					
Z0062456	TEMPORARY PAVEMENT	SO YD	2,630	2,630					
Z0064800	SELECTIVE CLEARING	UNIT	5	5					
Δ Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1		1				
∅ Z0076600	TRAINEES	HOUR	1000	1000					
∅ Z0076604	TRAINEES - TRAINING PROGRAM GRADUATE	HOUR	1000	1000					
X0323261	TEMPORARY SEDIMENT BASIN	EACH	6	6					
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	460	460					

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
345	106-S-N-1	KANE	167	18
			CONTRACT NO. 60110	
ILLINOIS FED. AID PROJECT				

USER NAME * USER#	DESIGNED - MTM	REVISED -
DRAWN - MTM	REVISED -	
PLOT SCALE * SCALE#	CHECKED - BA	REVISED -
PLOT DATE * DATE#	DATE - 3/31/14	REVISED -

SCALE: N.T.S. SHEET 15 OF 15 SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

FILE NAME: FILEL8  
10  
0042  
SHT\_PLAN