



- LEGEND:**
- PERIMETER EROSION BARRIER (SILT FENCE, SEE STD. 280001)
  - TEMPORARY DITCH CHECK
  - INLET FILTER/INLET & PIPE PROTECTION
  - STONE RIPRAP, CLASS A1
  - TEMPORARY EROSION CONTROL BLANKET
  - TEMPORARY SEDIMENT BASIN SIZE: 10'x5'x3'

- NOTES:**
1. INSTALL INLET FILTERS ON ALL OPEN STRUCTURES AND ALL FLARED END SECTIONS.
  2. TEMPORARY EROSION CONTROL BLANKET SHALL BE PLACED IN ACCORDANCE WITH THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS ON AREAS WITH SLOPES 1:3 OR STEEPER.
  3. THE CONTRACTOR SHALL CONSTRUCT "TEMPORARY CONSTRUCTION FENCE" AT THE FOLLOWING LOCATIONS: STA. 129+00 TO STA. 133+70 (EAST AND WEST SIDE OF US RTE. 20 / IL RTE. 47 / IL RTE. 72)
  3. THE CONTRACTOR SHALL CONSTRUCT THE WETLAND EXCLUSION FENCING AND THE "WETLAND NO INTRUSION" SIGNAGE PRIOR TO THE START OF THE CONSTRUCTION. THE COST OF THIS WORK SHALL BE INCLUDED IN THE COST OF "TEMPORARY CONSTRUCTION FENCE."

**SIGNAGE NOTE:**  
 "WETLAND NO INTRUSION" SIGNAGE CAN BE OBTAINED FROM STEVE LIPKE AT IDOT BUREAU OF MAINTENANCE, AND SHOULD BE RETURNED UNDAMAGED OR REPLACED AT THE END OF THE CONTRACT.

WETLAND EXCLUSION FENCING, 300 LF AND 36"x36" "WETLAND NO INTRUSION" SIGNAGE MOUNTED ON THE FENCE.

FILE NAME =	USER NAME = \$USER*	DESIGNED - MTM	REVISED - 5/2/14 BA	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>TEMPORARY EROSION &amp; SEDIMENT CONTROL DETAILS - STAGE II U.S. RTE 20 (NORTH JUNCTION)</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
\$MODELNAME*	PLOT SCALE = \$SCALE*	DRAWN - MTM	REVISOR -		345	106-S-N-1	KANE	167	50	CONTRACT NO. 60T10		
	PLOT DATE = \$DATE*	CHECKED - BA	REVISOR -		SCALE: 1"=50'	SHEET 5	OF 5 SHEETS	STA. 129+00	TO STA. 154+46	ILLINOIS FED. AID PROJECT		
		DATE - 3/31/14	REVISOR -									