

100% STATE

100% STATE

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE 0005					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE 0005					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	17	17					44201692	CLASS D PATCHES, TYPE II, 4 INCH	SO YD	675	675					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	77	77					44201694	CLASS D PATCHES, TYPE III, 4 INCH	SO YD	250	250					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	2114	2114					44201696	CLASS D PATCHES, TYPE IV, 4 INCH	SO YD	75	75					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					44201725	CLASS D PATCHES, TYPE I, 7 INCH	SO YD	25	25					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	193	193					44201729	CLASS D PATCHES, TYPE II, 7 INCH	SO YD	225	225					
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2	2					44201733	CLASS D PATCHES, TYPE III, 7 INCH	SO YD	125	125					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1336	1336					44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SO YD	75	75					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	3462	3462					60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	25	25					
42001300	PROTECTIVE COAT	SO YD	256	256					* 63100167	TRAFFIC BARRIER TERMINAL, TYPE I (SPECIAL) TANGENT	EACH	2	2					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	900	900					63200310	GUARDRAIL REMOVAL	FOOT	100	100					
42400800	DETECTABLE WARNINGS	SO FT	264	264					* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	15	15					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	15,914	15,914					67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	35318	35318					* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1					
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	17	17					67100100	MOBILIZATION	L SUM	1	1					
44000600	SIDEWALK REMOVAL	SO FT	900	900					* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1					
44201690	CLASS D PATCHES, TYPE I, 4 INCH	SO YD	30	30					70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
									70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
									70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
									70300100	SHORT TERM PAVEMENT MARKING	FOOT	96690	96690					

\* SPECIALTY ITEMS

Rev

FILE NAME	USER NAME	DESIGNED	REVISOR	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES				FALL RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN	REVISOR									2706	418BYRS-2	LAKE	28	3
		CHECKED	REVISOR											CONTRACT NO. 60V04		
		DATE	REVISOR									SCALE:		SHEET NO. OF SHEETS STA. TO STA.		
												FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				