

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE 0005					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE 0005				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 100% STATE 0005					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 100% STATE 0005				
20400800	FURNISHED EXCAVATION	CU YD	420	420					48101620	AGGREGATE SHOULDERS, TYPE B 10"	SO YD	107	107				
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNITS	621	621													
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	742	742					48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1317	1317				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNITS	72	72													
25000210	SEEDING, CLASS 2A	ACRE	0.15	0.15					* 63100167	TRAFFIC BARRIER TERMINAL, TYPE I (SPECIAL) TANGENT	EACH	7	7				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	14	14					63200310	GUARDRAIL REMOVAL	FOOT	350	350				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	14	14					67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL NO	4	4				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	14	14					67100100	MOBILIZATION	L SUM	1	1				
25100630	EROSION CONTROL BLANKET	SO YD	742	742					70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	212	212					70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1				
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, H50	TON	5829	5829					70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	75	75					70300100	SHORT TERM PAVEMENT MARKING	FOOT	29223	29223				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", H70	TON	11869	11869					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	83511	83511				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	141296	141296					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	9741	9741				
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SO YD	65	65					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	83511	83511				
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SO YD	800	800					78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1049	1049				
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SO YD	400	400					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	630	630				
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SO YD	500	500					x4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	95376	95376				
									70030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				

* SPECIALTY ITEMS

FILE NAME	USER NAME	DESIGNED	REVISED
DATE		DRAWN	REVISED
PLOT SCALE		CHECKED	REVISED
PLOT DATE		DATE	REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	126RS-5	KANE	22	3
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT			CONTRACT NO. 60Y07	