

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 100% STATE 0005					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 100% STATE 0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	82	82					44000600	SIDEWALK REMOVAL	SO FT	1385	1385					
25200110	SODDING, SALT TOLERANT	SO YD	82	82					44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	1430	1430					
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	4	4					44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	480	480					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	128	128					44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	480	480					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, W50	TON	3505	3505					48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	697	697					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	11021	11021					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	398	398					67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	302	302					67100100	MOBILIZATION	L SUM	1	1					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7063	7063					70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1					
42001300	PROTECTIVE COAT	SO YD	158	158					70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	7	7					70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	1385	1385					70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
42400800	DETECTABLE WARNINGS	SO FT	440	440					70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	79646	79646					70300100	SHORT TERM PAVEMENT MARKING	FOOT	96255	96255					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	2678	2678					70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	489	489					
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	10	10					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	92670	92670					

FILE NAME =	USER NAME = /azoom	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pr...of\av\ddr\azoom\031322505592-24-pln.dgn	DRAWN -	REVISED -	303			(21X,29V&132)RS-2	MCHENRY	34	3	
PLOT SCALE = 1/8" = 1'	CHECKED -	REVISED -	CONTRACT NO. 60V12							
PLOT DATE = 5/23/2014	DATE -	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS FED. AID PROJECT	

Rev.