

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN () WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

ľ	FILE NAME =	USER NAME = razeqam	DESIGNED -	REVISED - R. MIRS 09-15-97			ARTERIAL ROAD		F.A.U.	SECTION	COUNTY	TOTAL SHE SHEETS NO	ĘΤ
			DRAWN -	REVISED - R. MIRS 12-11-97	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				0197	3RS-2	LAKE	20 19	<u>"</u> —
			CHECKED -	REVISED -T. RAMMACHER 02-02-99							CONTRACT NO. 60VI5		
		PLOT DATE = 5/27/2014	DATE -	REVISED - C. JUCIUS 01-31-07		SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.		TO STA.	FED. ROA	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			\dashv