

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES					CONSTRUCTION TYPE CODE 0005				
CODE NO	ITEM	UNIT	0005									
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	625	625								
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	160	160								
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	50 FT	11247	11247								
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	50 FT	233	233								
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	29600	29600								
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	245	245								
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	120	120								
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	625	625								
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	160	160								
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	230	230								
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1								
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	100	100								
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	404	404								
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	132	132								

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES					CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	0005									
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	28956	28956								
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	3	3								
X7010410	SPEED DISPLAY TRAILER	CAL MO	0.3	0.3								
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1								
Z0030850	TEMPORARY INFORMATION SIGNING	50 FT	51.4	51.4								
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1								

* Specialty Items

FILE NAME	USER NAME	DESIGNED	REVISED
DATE	SCALE	CHECKED	REVISED
DATE	DATE	DATE	DATE

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES		F.P.P. RT#	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
SCALE	SHEET NO. OF SHEETS	856	EXHIBITS-4	WILL	21	4
CONTRACT NO. 60V44		FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT				