SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	20	20					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	5	5					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	5	5					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	5	5					
25200110	SODDING, SALT TOLERANT	SQ YD	20	20					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	16	16					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	428	428					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	216	216					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	998	998					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	12	12					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1158	1158					
42400800	DETECTABLE WARNINGS	SQ FT	230	230					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	10181	10181					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	12	12					
44000600	SIDEWALK REMOVAL	SQ FT	1158	1158					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	272	272					

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	85	85					
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	32	32					
50300300	PROTECTIVE COAT	SQ YD	137	137					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	12863	12863					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	182	182					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4221	4221					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1800	1800					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	135	135					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	163	163					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4287	4287					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	182	182					

*Specialty Items

FILE NAME = c:\pw_work\pwidot\hardnetfor\d03154\6\D157212-sht-plan.dgn	USER NAME = hardnetfor	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/23/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 1 OF 2 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
333	14RS-7	MCHENRY	22	3
		CONTRACT NO. 60V48		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT