

<b>ROUTE</b>	<b>SECTION</b>	<b>COUNTY</b>	<b>TOTAL SHEETS</b>	<b>SHEET NUMBER</b>
VARIOUS	2014-0061	COOK	14	7

CONTRACT: 60X81

LOCATION	COMB. CONC. C & G R&R (LF)	HMA SURF R&R VARIABLE DEPTH (SQYD)	SALT TOLERANT SODDING (SQYD)	SIDEWALK 5" R&R (SQFT) 18" CARRIAGE/ COURTESY	SIDEWALK 5" R&R (SQFT) 5' PARALLEL	SIDEWALK 8" R&R (SQFT) 5' PARALLEL	DRIVEWAY 8" R&R (SQFT)	DETECTABLE WARNINGS (ADA RAMPS) (SQFT)	CONC. CURB, TYPE B (LF)	REMARKS
6719 South Pulaski Road	30.0	5.0	0.0	0.0	0.0	120.0	30.0	20.0	0.0	Replace driveway apron including concrete gutter.
5816 South Rutherford	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	0.0	replace courtesy walk and carriage walk
6058 South Rutherford Avenue	80.0	13.4	13.4	0.0	0.0	0.0	0.0	0.0	0.0	Replace damaged curb on 61st Street and Rutherford Avenue Sides of House
6105 South Rutherford	20.0	3.4	0.0	0.0	0.0	0.0	350.0	20.0	30.0	replace alley apron
6234 South Rutherford Avenue	30.0	5.0	0.0	60.0	0.0	0.0	0.0	0.0	0.0	Replace Entire Curb and Carriage Walk (Property Line to Property Line)
5722 South Sayre Avenue	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	2 Sidewalk Squares In Front of Driveway Apron
6801 South Tripp	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	replace the 2 damaged sidewalk squares near the garage
3901 West 55th Place	0.0	0.0	0.0	0.0	0.0	0.0	350.0	20.0	30.0	replace alley apron
6135 West 55th Street	0.0	0.0	0.0	0.0	0.0	0.0	350.0	20.0	30.0	Replace Driveway Apron on Moody Avenue Side
6157 West 55th street	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	replace 5 damaged sidewalk squares
4028 West 56th Place	0.0	0.0	0.0	0.0	120.0	0.0	0.0	0.0	0.0	4 Sidewalk Squares
4059 West 56th Place	0.0	0.0	0.0	0.0	660.0	0.0	0.0	0.0	0.0	22 Sidewalk Squares on Karlov Avenue Side of Address/House
3912 West 56th street	0.0	0.0	0.0	0.0	90.0	0.0	0.0	0.0	0.0	replace the 3 damaged sidewalk squares
4058 West 57th Place	0.0	0.0	0.0	0.0	60.0	0.0	350.0	0.0	60.0	Alley Apron, Entire Curb Around Driveway Apron, 2 Sidewalk Squares on Karlov Avenue Side of Address/House
4106 West 57th Place	0.0	0.0	0.0	15.0	180.0	0.0	0.0	0.0	0.0	6 Sidewalk Squares, 2 Courtesy Walks & Carriage Walk
4024 west 57th street	15.0	2.5	2.5	0.0	0.0	0.0	0.0	0.0	0.0	replace 15 feet of damaged curb and gutter
4111 West 58th Street	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	2 Sidewalk Squares
4123 West 58th Street	10.0	1.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	Replace Section of Cracked/Broken Curb
3942 west 59th street	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	0.0	replace the courtesy walk and carriage walk
4116 West 59th Street	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	2 Sidewalk Squares - Concrete Parkway Cave-In
6659 West 59th Street	0.0	0.0	0.0	0.0	0.0	0.0	350.0	20.0	30.0	Driveway Apron
6110 West 59th Street	0.0	0.0	0.0	15.0	90.0	0.0	0.0	0.0	0.0	3 Sidewalk Squares & Courtesy Walk
6338 West 59th Street	30.0	5.0	1.7	30.0	0.0	0.0	0.0	0.0	0.0	Replace Cracked Curb
5938 West 60th Street	10.0	1.7	1.7	0.0	0.0	0.0	0.0	0.0	0.0	Replace cracked curb in front of manhole sewer
<b>SUB-TOTAL</b>	<b>225.0</b>	<b>37.7</b>	<b>19.3</b>	<b>240.0</b>	<b>1590.0</b>	<b>120.0</b>	<b>1780.0</b>	<b>100.0</b>	<b>180.0</b>	

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**