ROUTE: EB Armytrail Road (Entrance Ramp to NB I-355)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
EB Army Trail Road			Ramp	15	6	90	10
			Ramp	15	50	750	83
			Ramp	6	100	600	67
			Ramp	8	50	400	44
	PCC/HMA Joint		Ramp	15	6	90	10
		TOTALS:			**212 FT**		**214 SY**

ROUTE: EB I-290(NB I-355 Feeder Ramp)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
NB I-355			1	12	6	72	8
			2	12	6	72	8
			1	12	8	96	11
			2	6	40	240	27
			1	12	3	36	4
			1	12	3	36	4
	EB I-290		2	12	3	36	4
		TOTALS:			**69 FT**		**65 SY**

ROUTE: EB I-290 (I-355 to IL 83(Kingery Highway))

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
I-355		EB	2	12	6	72	8
		EB	3	12	6	72	8
		EB	3	12	6	72	8
		EB	2	12	6	72	8
		EB	3	12	6	72	8
		EB	3	12	6	72	8
		EB	2	12	6	72	8
		EB	2	12	6	72	8
		EB	2	12	6	72	8
		EB	3	12	6	72	8
		EB	2	12	6	72	8
		EB	2	12	6	72	8
		EB	3	12	6	72	8
		EB	2	12	6	72	8
	Mill Road Bridge	EB	3	12	6	72	8
Mill Road Bridge		EB	3	12	6	72	8
		EB	2	12	6	72	8
	IL 83(Kingery Highway)	EB	2	12	6	72	8
		TOTALS:			**108 FT**		**144 SY**

ROUTE: EB I-290 (SB IL 83(Kingery Highway) Exit Ramp)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
EB I-290				15	3	45	5
				15	3	45	5
				15	3	45	5
				15	6	90	10
				15	3	45	5
				15	3	45	5
				15	3	45	5
				15	6	90	10
				15	6	90	10
				15	3	45	5
				15	6	90	10
				15	3	45	5
				15	3	45	5
				15	6	90	10
				15	6	90	10
				15	3	45	5
				15	6	90	10
				15	3	45	5
				15	3	45	5
				15	6	90	10
				15	3	45	5
				15	6	90	10
				15	6	90	10
	SB IL 83(Kingery Highway)			15	6	90	10
		TOTALS:			**105 FT**		**175 SY**

ROUTE: WB I-290 (SB IL 83(Kingery Highway) Exit Ramp)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
WB I-290				15	6	90	10
				15	3	45	5
				15	3	45	5
				15	3	45	5
				15	3	45	5
				15	3	45	5
				15	3	45	5
				15	3	45	5
				6	80	480	53
				15	6	90	10
				15	6	90	10
				15	6	90	10
				15	3	45	5
				15	6	90	10
	SB IL 83(Kingery Highway)			30	6	180	20
		TOTALS:			**140 FT**		**163 SY**

*COOK, DUPAGE AND LAKE

FILE NAME = c:\pw_work\pwidot\pencepl\d038248b\HMA-Expressway-North.dgn	USER NAME = PencePL	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = 4/11/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INTERMITTENT RESURFACING SCHEDULE
ARMY TRAIL RD. AND I-290

SCALE: | SHEET OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2014-029RS	VARIOUS*	25	9

CONTRACT NO. 60Y15

ILLINOIS FED. AID PROJECT