

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0044				CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0044				
67100100	MOBILIZATION	L SUM	1	1				* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	2				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	132	132				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2	2				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1												
X6020294	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1												
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	290	290												
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1												
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	2	2												
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4												
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	425	425												
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1												
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1												

* 85000200 MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION
 * 88600600 DETECTOR LOOP REPLACEMENT
 Z0073510 TEMPORARY TRAFFIC SIGNAL TIMING



12 * Specialty Items

Rev.

Rev. 7-18-14

FILE NAME :	USER NAME : gulliamer2	DESIGNED -	REVISED -
C:\pwworking\gulliamer2\p00359037\0136814-att-pln.dgn		DRAWN -	REVISED -
PLOT SCALE * 100.0000 / 1/16		CHECKED -	REVISED -
PLOT DATE * 6/11/2014		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 43 (HARLEM AVE.)
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	3(34-T(14))	COOK	16	4
CONTRACT NO. 60Y36				
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT				