CODE NO.	ITEM	UNIT	TOTAL QUANTITY 100% STATE	ROADWAY 100% STATE	FIBER OPTIC CONDUIT 100% MCHENRY COUNTY	TRAFFIC SIGNALS: US RTE 14 & DOTY ROAD 93.3% STATE 6.7% WOODSTOCK	TRAFFIC SIGNALS: US RTE 14 & W LAKE SHORE DR 95% STATE 5% WOODSTOCK	TRAFFIC SIGNALS: EMERGENCY VEHICLE PREEMPTION 100% WOODSTOCK	TRAFFIC SIGNALS: INTERCONNECT 100% STATE	TRAFFIC SIGNALS: US RTE 14 & LAKE SHORE DR 90% STATE 10% WOODSTOCK	MULTI-USE PATH 80% STATE 20% MCCD	WATER MAIN AND SANITARY SEWER 100% WOODSTOCK	WATER MAIN AND SANITARY SEWER 100% STATE
			URBAN	CONSTRUCTION CODE									
				0003	0021	0021	0021	0021	0021	0021	0028	0043	0043
•81400100	HANDHOLE	EACH	25		3	4	3		10	5			
•81400200	HEAVY-DUTY HANDHOLE	EACH	11			3	4			4			
•81400300	DOUBLE HANDHOLE	EACH	5			2	2			1			
•85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1									
•86400100	TRANSCEIVER - FIBER OPTIC	EACH	3			1	1			1			
•87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	12,557		4800				7,757				
•87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,219				1,021			198			
•87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	3,385				2,422	447		516			
•87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	7,490			1,760	4,438			1,292			
•87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2,724			1,094				1,630			
•87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	7,420			2,256	2,904			2,260			
•87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	173			68	72			33			
•87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	2,276			696	1,000			580			
•87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1				1						
•87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	4			1	3						

• SPECIALTY ITEM

FILE NAME = C:\Projects\US14\LSD-LucasRd-LongTran\MicroStation Design Files\Sheet\SUDDD$NW.DGN	USER NAME = $$user$$	DESIGNED -	REVISED -
exp U.S. Services Inc. Chicago, IL BUILDINGS-EARTH & ENVIRONMENT-ENERGY INDUSTRIAL-INFRASTRUCTURE-SUSTAINABILITY	PLOT SCALE = 100.0000 ' / in.	DRAWN - AMB	REVISED -
	PLOT DATE = 6/18/2014	CHECKED - BRH	REVISED -
		DATE - 11/01/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
U.S. ROUTE 14

SUMMARY OF QUANTITIES - I

SCALE: N.T.S. | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	27R-2	MCHENRY	673	4N½
		CONTRACT NO. 62268		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		