

78100300 REPLACEMENT REFLECTOR TOTAL 24 EACH				
LOCATION	FROM STATION	TO STATION	AVE. SPACING	SUBTOTALS
US RTE 14	156+00	165+40	80	24

X0300266 WOODEN FENCE REMOVAL TOTAL 260 FOOT				
LOCATION	FROM STATION	TO STATION	SUBTOTALS	
LILY POND RD	802+53.30	804+75.41	260	

X6061100 CONCRETE MEDIAN, TYPE SB (SPECIAL) TOTAL 17,397 SQ FT					
LOCATION	FROM STATION	TO STATION	OFFSET	SUBTOTALS	
US RTE 14	348+61.19	350+80.23	LT	1308.3	
US RTE 14	351+44.14	353+63.24	RT	1312.6	
US RTE 14	362+80.74	364+98.74	LT	1304.1	
US RTE 14	366+07.60	368+25.60	RT	1304.1	
US RTE 14	393+58.81	396+76.81	LT	1904.1	
US RTE 14	397+92.33	400+10.33	RT	1304.1	
US RTE 14	427+06.45	430+23.43	LT	1892.9	
US RTE 14	431+02.87	432+50.00	RT	876.0	
US RTE 14	432+50.00	434+12.90	RT	974.15	
US RTE 14	448+85.00	451+03.00	LT	1304.1	
US RTE 14	451+62.00	453+80.00	RT	1304.1	
US RTE 14	465+06.31	467+24.31	LT	1304.1	
US RTE 14	468+10.40	470+28.38	RT	1304.1	

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL TOTAL 829 EACH				
LOCATION	FROM STATION	TO STATION	AVE. SPACING	SUBTOTALS
US RTE 14	129+22	168+28	80	98
US RTE 14	129+67	168+28	80	98
US RTE 14	150+47	152+65	40	6
US RTE 14	150+47	154+06	40	10
US RTE 14	152+08	153+74	40	5
US RTE 14	155+31	158+98	40	9
US RTE 14	154+97	160+27	40	14
US RTE 14	157+68	160+27	40	7
US RTE 14	155+53	157+72	40	6
US RTE 14	166+20	168+60	40	6
US RTE 14	166+20	167+55	40	4
US RTE 14	166+85	168+35	40	4
US RTE 14	325+15	327+85	40	8
US RTE 14	325+40	331+65	80	16
US RTE 14	325+25	328+75	40	10
US RTE 14	326+65	328+75	40	6
US RTE 14	325+45	331+65	40	16
US RTE 14	325+40	331+65	80	16
US RTE 14	331+65	340+05	40	42
US RTE 14	340+05	344+25	80	10
US RTE 14	344+25	353+15	80	12
US RTE 14	353+15	357+40	80	10
US RTE 14	357+40	365+00	40	38
US RTE 14	366+15	373+70	40	38
US RTE 14	373+70	387+75	80	36
US RTE 14	387+75	396+60	40	44
US RTE 14	397+80	405+65	40	40
US RTE 14	405+65	431+50	80	64
US RTE 14	432+60	447+40	80	38
US RTE 14	447+40	456+15	80	12
US RTE 14	456+15	464+90	80	22
US RTE 14	466+90	475+35	80	22
US RTE 14	475+35	491+25	80	20
US RTE 14	491+25	493+00	40	8
US RTE 14	362+95	365+00	40	6
US RTE 14	362+95	365+00	40	6
US RTE 14	366+15	367+15	40	4
US RTE 14	366+15	368+10	40	6
US RTE 14	394+65	396+50	40	6
US RTE 14	397+80	400+15	40	6

X4402020 CONCRETE MEDIAN SURFACE REMOVAL TOTAL 3,121 SQ FT				
LOCATION	FROM STATION	TO STATION	AREA (SQ FT)	SUBTOTALS
US RTE 14	168+16	169+59	306.15	306
US RTE 14	326+16	331+65	2814.79	2814.79

X4402800 ISLAND PAVEMENT REMOVAL TOTAL 158 SQ YD				
LOCATION	FROM STATION	TO STATION	AREA (SQ FT)	SUBTOTALS
US RTE 14	325+19	325+52	613.66	68
US RTE 14	325+28	326+70	805.2	89

60608582 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24 TOTAL 200 FOOT					
LOCATION	FROM STATION	TO STATION	OFFSET	SUBTOTALS	
US RTE 14	325+29.00	326+56.46	LT	127	
US RTE 14	328+07.98	328+80.44	RT	72	

60608552 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06 TOTAL 140 FOOT					
LOCATION	FROM STATION	TO STATION	OFFSET	SUBTOTALS	
US RTE 14	325+25.00	326+56.46	LT	140.0	

T:\DOCUMENTS\1934\9901\CIVIL\DCN\SC000.PY.DGN
 exp U.S. Services Inc.
 BUILDINGS-EARTH & ENVIRONMENT-ENERGY
 INDUSTRIAL-INFRASTRUCTURE-SUSTAINABILITY
 11-07-2013 16:19:01