EXISTING SIGN SCHEDULE

		EXISTING LOCATION		PROPOSED LOCATION						DIMENSIONS		AREA	72400100	72400200	72400500	72400800	72400710	X7240600		72800100	73000100	X7280105
SIGN I.D.	ROAD	STATION	OFFSET	RELOCATED STATION	RELOCATED OFFSET	SIGN DESCRIPTION	EX. GROUND MOUNTING TYPE	PROPOSED GROUND MOUNTING TYPE	TYPE/I.D.	HEIGHT	WIDTH	SF	REMOVE SIGN PANEL ASSEMBLY - TYPE A	REMOVE SIGN PANEL ASSEMBLY - TYPE B	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	RELOCATE SIGN PANEL - TYPE 1	REMOVE AND RE-ERECT EXISTING SIGN	SIGN PANEL ASSEMBLY TO REMAIN	TELESCOPING STEEL SIGN SUPPORT	WOOD SIGN SUPPORT	TELESCOPING STEEL SIGN SUPPORT (SPECIAL)
										FT	FT	SF	EACH	EACH	EACH	EACH	SQ FT	EACH	EACH	FT	FT	FT
S-40	US ROUTE 14	154+61	27' R			INTERSECTION WARNING	WOOD POST		W2-1	3.00	3.00	9.00		1								
S-40A						COLLEGE ENT (LEFT)/LUCAS R			CUSTOM	1.25	3.50	4.38										
S-41	US ROUTE 14	157+05	22' R	493+00	46' R	MCHENRY 14/24	METAL POST	TELESCOPING	CUSTOM	1.50	1.50	2.25	1		1					14		
S-41A	US ROUTE 14	157+05	22' R	493+00	46' R	MCHENRY 14/24				1.50	1.50	2.25										
S-42	US ROUTE 14	143+05	27' L			SPEED LIMIT 50			R2-1	3.00	2.50	7.50	1									
S-43	US ROUTE 14	140+45	27' L			SIDE ROAD (RIGHT)			W2-2R	3.00	3.00	9.00		1								
S-43A						RIDGEFIELD ROAD			CUSTOM	0.75	3.00	2.25										
S-44	RIDGEFIELD RD NORTH	430+79	45' L			STOP SIGN	WOOD POST		R1-1	3.00	3.00	9.00	1									
S-45	US ROUTE 14	123+83	27' L			SPEED LIMIT 50	METAL POST		R2-1	3.00	2.50	7.50	1									
S-46	US ROUTE 14	120+25	30' L			NO PASSING ZONE	WOOD POST		W14-3	4.95	4.00	9.90		1								
S-47	US ROUTE 14	109+70	30' L			CURVE SIGN (LEFT)	WOOD POST		W1-2L	3.00	3.00	9.00	1									
S-48	US ROUTE 14	102+95	30' L			SIDE STREET (RIGHT)	WOOD POST		W2-2R	3.00	3.00	9.00		1								
S-48A						LILY POND ROAD			CUSTOM	0.75	3.00	2.25										
S-49	US ROUTE 14	101+92	30' L			CHEVRON SIGN	METAL POST		W1-8	2.50	2.00	5.00		1								
S-49A						CHEVRON SIGN			W1-8	2.50	2.00	5.00										
S-50	US ROUTE 14	100+59	32' L			CHEVRON SIGN	METAL POST		W1-8	2.50	2.00	5.00		1								
S-50A						CHEVRON SIGN			W1-8	2.50	2.00	5.00										
S-52	US ROUTE 14	98+76	30' L			CHEVRON SIGN	METAL POST		W1-8	2.50	2.00	5.00		1								
S-52A						CHEVRON SIGN			W1-8	2.50	2.00	5.00										
S-53	US ROUTE 14	97+76	26' L			NO PARKING ALONG HIGHWAY	METAL POST		CUSTOM	1.50	1.00	1.50	1									
S-54	LILY POND ROAD	300+41	16' L			STOP SIGN	METAL POST		R1-1	3.00	3.00	9.00	1									
S-55	LILY POND ROAD	300+55	18' L			ROUTE 14	METAL POST		M1-4	2.00	2.00	4.00	1									
S-55A						TWO DIRECTIONAL ARROW			M6-4	1.25	1.75	2.19										
S-56	US ROUTE 14	94+82	29' L	428+25	60' L	ADOPT A HIGHWAY	METAL POST	TELESCOPING	CUSTOM	2.50	2.50	6.25		1		1				19.5		
S-56A						KEEP WOODSTOCK CLEAN			CUSTOM	2.50	2.50	6.25										
S-57	US ROUTE 14	92+98	26' L			EXCESSIVE ENGINE BRAKING NOISE PROHIBITE	METAL POST		R5-I106	3.50	3.00	10.50		1								
S-58	US ROUTE 14	85+06	30' L			UNLAWFUL TO PASS STOPPED SCHOOL BUS FROM OTHER DIRECTION	METAL POST		CUSTOM	2.50	2.50	6.25	1									
S-59	US ROUTE 14	77+00	25' L			SPEED LIMIT 50	METAL POST		R2-1	3.00	2.50	7.50	1									
S-60	US ROUTE 14	70+25	25' L			DO NOT PASS	WOOD POST		R4-1	4.00	3.00	12.00		1								
S-61	US ROUTE 14	67+24	28' L			SIGNAL AHEAD	WOOD POST		W3-3	3.00	3.00	9.00		1								
S-61A						DOTY ROAD			CUSTOM	0.75	3.00	2.25										
S-62	US ROUTE 14	64+97	29' L			HOSPITAL	METAL POST		D9-2	2.00	2.00	4.00	1									
S-62A						DIRECTIONAL ARROW (LEFT)			M6-1	1.25	1.75	2.19										
S-64	US ROUTE 14	57+94	26' L			CURVE SIGN (RIGHT)	WOOD POST		W1-2	3.00	3.00	9.00	1									
S-65	US ROUTE 14	39+00	30' L			INTERSECTION WARNING	WOOD POST		W2-1	3.00	3.00	9.00		1								
S-65A						LAKE SHORE DRIVE			CUSTOM	0.75	3.00	2.25										
S-66	US ROUTE 14	30+30	38' L			RIGHT ONLY	METAL POST		W3-5R	2.50	2.50	6.25	1									
S-67	US ROUTE 14	30+00	58' L			RTE 14	METAL POST		CUSTOM	0.75	1.50	1.13	1									
S-67A						LAKE SHORE DR			CUSTOM	0.75	3.00	2.25										
S-68	LAKE SHORE DRIVE	46+40	30' R	46+30	31' R	BEGIN CLASS II TRUCK ROUTE	METAL POST	TELESCOPING	R5-I101	2.50	2.00	5.00	1		1					16		
S-69	LAKE SHORE DRIVE	45+73	41' L			STOP SIGN	METAL POST		R1-1	3.00	3.00	9.00	1									
S-70	US ROUTE 14	28+50	35' L			SPEED LIMIT 50	METAL POST		R2-1	3.00	2.50	7.50	1									
S-71	US ROUTE 14	197+92	25' L			NO PASSING ZONE	WOOD POST		W14-3	4.95	4.00	9.90		1								
S-72	US ROUTE 14	186+77	25' L			SPEED LIMIT 55	METAL POST		R2-1	3.00	2.50	7.50	1									
S-73	US ROUTE 14	182+06	30' L			DIVIDED HIGHWAY (ROAD) BEGINS	WOOD POST		W6-1	4.00	4.00	16.00		1								
S-74	US ROUTE 14	177+30	30' L	333+10	59' L	ADOPT A HIGHWAY	METAL POST	TELESCOPING	CUSTOM	2.00	2.50	5.00		1		1				20.0		
S-74A									CUSTOM	2.50	2.50	6.25										
S-75	US ROUTE 14	171+75	30' R			LEFT ONLY	METAL POST		R3-5L	2.50	2.00	5.00	1									
S-76	US ROUTE 14	169+77	37' L			DO NOT ENTER	METAL POST		R5-1	2.50	2.50	6.25		1								
S-76A						RIGHT ONLY			R3-5R	2.00	2.00	4.00										
S-77	US ROUTE 14	169+32	15' R			STOP HERE ON RED	METAL POST		R10-6a	2.50	2.00	5.00	1									
S-78	US ROUTE 14	169+18	16' R			LEFT TURN SIGNAL	SIGNAL POST		R10-10	2.50	2.00	5.00										
S-79	RIDGEFIELD RD NORTH	431+68	90' R			RIDGEFIELD ROAD	METAL POST		CUSTOM	0.75	3.00	2.25										
S-79A						RIDGEFIELD ROAD			CUSTOM	0.75	3.00	2.25										
S-79B						U.S. RTE 14			CUSTOM	0.75	3.00	2.25	1									
S-79C						U.S. RTE 14			CUSTOM	0.75	3.00	2.25										
S-80	RIDGEFIELD RD NORTH	431+70	29' L	851+35	37' L	END CLASS II TRUCK ROUTE	WOOD POST	TELESCOPING	R5-I101	2.50	2.00	5.00	1		1							16.50

..\SIGN08_14.DGN ..\TTB08#JJ.DGN ..\SIGN08_14.DGN
11-08-2013, 9:28:11 HECHTBR T:\DOCUMENT\193439B\CIVIL\DGN\SIGN08_16.DGN

FILE NAME = $FILEL$	USER NAME = HECHTBR	DESIGNED -	REVISED -	**STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION** U.S. ROUTE 14
		DRAWN - BRH	REVISED -	
exp U.S. Services Inc. Chicago, IL BUILDINGS•EARTH & ENVIRONMENT•ENERGY INDUSTRIAL•INFRASTRUCTURE•SUSTAINABILITY	PLOT SCALE = $SCALE$	CHECKED - TMH	REVISED -	
	PLOT DATE = $DATE$	DATE - 11/01/13	REVISED -	

EXISTING SIGN SCHEDULE – II

SCALE: N.T.S. | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	27R-2	MCHENRY	673	388
		CONTRACT NO. 62268		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		