

EXISTING SIGN SCHEDULE

SIGN I.D.	ROAD	EXISTING LOCATION		PROPOSED LOCATION		SIGN DESCRIPTION	EX. GROUND MOUNTING TYPE	PROPOSED GROUND MOUNTING TYPE	TYPE/I.D.	DIMENSIONS		AREA SF	72400100	72400200	72400500	72400600	72400710	X7240600	72800100	73000100	X7280105	
		STATION	OFFSET	RELOCATED STATION	RELOCATED OFFSET					HEIGHT FT	WIDTH FT		REMOVE SIGN PANEL ASSEMBLY - TYPE A EACH	REMOVE SIGN PANEL ASSEMBLY - TYPE B EACH	RELOCATE SIGN PANEL ASSEMBLY - TYPE A EACH	RELOCATE SIGN PANEL ASSEMBLY - TYPE B EACH	RELOCATE SIGN PANEL - TYPE 1 SQ FT	REMOVE AND RE-ERECT EXISTING SIGN EACH	SIGN PANEL ASSEMBLY TO REMAIN EACH	TELESCOPING STEEL SIGN SUPPORT FT	WOOD SIGN SUPPORT FT	TELESCOPING STEEL SIGN SUPPORT (SPECIAL) FT
S-80	RIDGEFIELD RD NORTH	431+70	29' L	851+35	37' L	END CLASS II TRUCK ROUTE	WOOD POST	TELESCOPING	R5-I101	2.50	2.00	5.00	1		1							16.50
S-81	RIDGEFIELD RD NORTH	432+47	25' R	851+65	38' R	MCHENRY V25 COUNTY	METAL POST	TELESCOPING	M1-5	2.00	2.00	4.00	1									
S-81A		432+46	45' L			BEGIN CLASS II TRUCK ROUTE			R5-I101	2.50	2.00	5.00					5					
S-82	RIDGEFIELD RD NORTH	432+46	45' L			NO TRUCKS	WOOD POST		R5-2	2.00	2.00	4.00	1						1			
S-83	RIDGEFIELD RD NORTH	433+60	21' R	852+70	38' R	MCHENRY COUNTY ADOPT A HIGHWAY	METAL POST		CUSTOM	2.50	2.50	6.25		1		1						
S-83A		436+33	53' L			ERICKSONS KENNELS			CUSTOM	1.50	2.50	3.75										
S-84	RIDGEFIELD RD NORTH	436+33	53' L			STOP SIGN AHEAD	WOOD POST		W3-1A	3.00	3.00	9.00	1						1			
S-85	US ROUTE 14	169+30	79' R			ONE WAY	SIGNAL POST		R6-1R	1.00	3.00	3.00										
S-85A	US ROUTE 14	169+30	79' R			ONE WAY	SIGNAL POST		R6-1L	1.00	3.00	3.00										
S-86	US ROUTE 14	167+31	14' R			LEFT ONLY	METAL POST		R3-5L	2.50	2.00	5.00	1									
S-87	US ROUTE 14	169+17	29' R			LEFT TURN SIGNAL	SIGNAL POST		R10-10	2.50	2.00	5.00										
S-88	US ROUTE 14	167+68	35' R			STOP HERE ON RED	METAL POST		R10-6a	2.50	2.00	5.00	1									
S-89	US ROUTE 14	168+42	31' R			LEFT TURN SIGNAL	SIGNAL POST		R10-10	2.50	2.00	5.00										
S-90	US ROUTE 14	163+75	80' R			RIGHT LANE ENDS	WOOD POST		W9-1	3.00	3.00	9.00	1									
<b>TOTAL:</b>												48	35	4	7	5	1	2	123.5	35	49	

I:\SGN00\14.DGN...T1B000.LJJ.DGN...SGN00\_14.DGN...HECHTBR T:\DOCUMENT\1934\9901\CIVIL\DCN\SGN00\_14.DGN  
 11-08-2013, 9:28:13

FILE NAME = \*FILEL\*  
 USER NAME = HECHTBR  
 DESIGNED -  
 DRAWN - BRH  
 CHECKED - TMH  
 DATE - 11/01/13  
 PLOT SCALE = \*SCALE\*  
 PLOT DATE = \*DATE\*  
 exp U.S. Services Inc. BUILDINGS-EARTH & ENVIRONMENT-ENERGY INDUSTRIAL-INFRASTRUCTURE-SUSTAINABILITY

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**  
 U.S. ROUTE 14

**EXISTING SIGN SCHEDULE - III**

SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	27R-2	MCHENRY	673	389
CONTRACT NO. 62268				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				