

URBAN SUMMARY OF QUANTITIES

PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	TRAFFIC SIGNALS											WATER MAIN AND SANITARY SEWER		
				ROADWAY			SHARED-USE PATH	LIGHTING	US 14 & LUCAS ROAD	US 14 & RIDGEFIELD ROAD SOUTH	US 14 & IL 176	US 14 & WOODSTOCK STREET	US 14 & CRYSTAL LAKE AVE	EMERGENCY VEHICLE PROTECTION/ILLUMINATED STREET NAME SIGNS	INTERCONNECT	100% STATE	100% CRYSTAL LAKE
				100% STATE	MCHENRY COUNTY COLLEGE 100%	80% STATE 20% MCO	100% STATE	MCHENRY COUNTY COLLEGE 100%	93.3% STATE 6.7% MCHENRY COUNTY	100% STATE	90% STATE 10% CRYSTAL LAKE	100% CRYSTAL LAKE	100% STATE	100% STATE	100% STATE	100% CRYSTAL LAKE	
				0003	0003	0028		0021	0021	0021	0021	0021	0021	0021	0021	0043	0043
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	24	24													
60248700	VALVE VAULTS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1														1
60248900	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3														3
60249010	VALVE VAULTS, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	8														8
60250200	CATCH BASINS TO BE ADJUSTED	EACH	2	2													
60255500	MANHOLES TO BE ADJUSTED	EACH	16	16													
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	7														7
60500040	REMOVING MANHOLES	EACH	15	15													
60500050	REMOVING CATCH BASINS	EACH	56	56													
60500060	REMOVING INLETS	EACH	4	4													
60500080	REMOVING CATCH BASINS TO MAINTAIN FLOW	EACH	3	3													
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	1	1													
60500405	FILLING VALVE VAULTS	EACH	4														4
60600605	CONCRETE CURB, TYPE B	FOOT	1,611	1,440	127	44											
60603800	COMBINATION CONCRETE CURB AND CUTTER, TYPE B-6.12	FOOT	2,603	2,133	470												

* SPECIALTY ITEM

Rev. 7-18-14

FILE NAME = 5:\1506\15000 Sheets\15162517-151-500.dgn	USER NAME = USERNAME	DESIGNED -	REVISIONS -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 100.0000' / 1" =	DRAWN -	REVISIONS -	305					27R-3	MCHENRY	431	110	
PLOT DATE = 6/17/2014	CHECKED -	REVISIONS -	SCALE: NONE SHEET NO. 110 OF 431 SHEETS STA. TO STA.				CONTRACT NO. 62517					
	DATE -	REVISIONS -	ILLINOIS FED. AID PROJECT									