

SUMMARY OF QUANTITIES

URBAN

PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY		SHARED-USE PATH	LIGHTING	TRAFFIC SIGNALS					EMERGENCY VEHICLE PROTECTION ILLUMINATED STREET NAME SIGNS	INTERCONNECT	WATER MAIN AND SANITARY SEWER		
				100% STATE	MCHENRY COUNTY COLLEGE 100%			80% STATE 20% MCCC	100% STATE	US 14 & LUCAS ROAD	US 14 & RIDGEFIELD ROAD SOUTH	US 14 & IL 176			US 14 & WOODSTOCK STREET	US 14 & CRYSTAL LAKE AVE	100% CRYSTAL LAKE
				0003	0003	0028	0021	0021	0021	0021	0021	0021	0021	0021	0021	0043	0043
81400100	HANDHOLE	EACH	39						5	4	7	4	4		15		
81400200	HEAVY-DUTY HANDHOLE	EACH	16						4	3	4	2	3				
81400300	DOUBLE HANDHOLE	EACH	9						2	1	2	2	2				
81603090	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	4,500				4,500										
81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	80				80										
81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	4,700				4,700										
82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	22				22										
82500360	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 100AMP	EACH	1				1										
83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	18				18										
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	180				180										
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	18				18										
84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	19				19										
84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	16				16										
84200804	REMOVAL OF POLE FOUNDATION	EACH	16				16										
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1														
86400100	TRANSCEIVER - FIBER OPTIC	EACH	5						1	1	1	1	1				

* SPECIALTY ITEM

Rev. 7-18-14