

**URBAN SUMMARY OF QUANTITIES**

PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	TRAFFIC SIGNALS												WATER MAIN AND SANITARY SEWER	
				ROADWAY		SHARED-USE PATH	LIGHTING	US 14 & LUCAS ROAD	US 14 & RIDGEFIELD ROAD SOUTH	US 14 & IL 176	US 14 & WOODSTOCK STREET	US 14 & CRYSTAL LAKE AVE	EMERGENCY VEHICLE PROTECTION/ILLUMINATED STREET NAME SIGNS	INTERCONNECT	100% STATE	100% CRYSTAL LAKE	
				100% STATE	MCHENRY COUNTY COLLEGE 100%	80% STATE 20% MCHENRY COUNTY	100% STATE	MCHENRY COUNTY COLLEGE 100%	93.3% STATE 6.7% MCHENRY COUNTY	100% STATE	90% STATE 10% CRYSTAL LAKE	90% STATE 10% CRYSTAL LAKE	100% CRYSTAL LAKE	100% STATE	100% STATE	100% CRYSTAL LAKE	
				0003	0003	0028	0021	0021	0021	0021	0021	0021	0021	0021	0043	0043	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,763	1,727	36												
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,763	1,727	36												
* 25100115	MULCH, METHOD 2	ACRE	8.90	8.90													
* 25100630	EROSION CONTROL BLANKET	SO YD	85,813	85,813													
* 25200110	SODDING, SALT TOLERANT	SO YD	8,555	8,555													
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	191	191													
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2,660	2,660													
28000305	TEMPORARY DITCH CHECKS	FOOT	1,848	1,848													
28000400	PERIMETER EROSION BARRIER	FOOT	14,018	14,018													
28000500	INLET AND PIPE PROTECTION	EACH	22	22													
28000510	INLET FILTERS	EACH	238	238													
28001000	AGGREGATE (EROSION CONTROL)	TON	7	7													
28100105	STONE RIPRAP, CLASS A3	SO YD	131	131													
28200200	FILTER FABRIC	SO YD	131	131													
* 30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	117,174	115,140	2,034												

\* SPECIALTY ITEM