

URBAN
SUMMARY OF QUANTITIES

PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY		SHARED-USE PATH	LIGHTING	TRAFFIC SIGNALS							WATER MAIN AND SANITARY SEWER		
				100% STATE	MCHENRY COUNTY COLLEGE 100%			80% STATE 20% MCCO	100% STATE	MCHENRY COUNTY COLLEGE 100%	93.3% STATE 6.7% MCHENRY COUNTY	100% STATE	90% STATE 10% CRYSTAL LAKE	90% STATE 10% CRYSTAL LAKE	EMERGENCY VEHICLE PROTECTION ILLUMINATED STREET NAME SIGNS	INTERCONNECT	100% STATE
				0003	0003	0028	0021	0021	0021	0021	0021	0021	0021	0021	0021	0043	0043
40701861	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9"	SO YD	4,330	2,895	1,435												
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SO YD	84,159	83,770	389												
42001300	PROTECTIVE COAT	SO YD	113,466	112,993	473												
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	1,275	1,275													
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	21,025	21,025													
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SO FT	764	764													
42400800	DETECTABLE WARNINGS	SO FT	412	278		134											
44000100	PAVEMENT REMOVAL	SO YD	87,861	86,501	1,360												
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	2,044	1,512	532												
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	11,350	11,350													
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	5,658	5,567	91												
44000300	CURB REMOVAL	FOOT	1,940	1,790	150												
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	11,773	11,773													
44000600	SIDEWALK REMOVAL	SO FT	17,304	17,304													
44003100	MEDIAN REMOVAL	SO FT	2,032	2,032													

* SPECIALTY ITEM

ILLINOIS FED. AID PROJECT CONTRACT NO. 62517