

URBAN SUMMARY OF QUANTITIES

PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	TRAFFIC SIGNALS												WATER MAIN AND SANITARY SEWER	
				ROADWAY		SHARED-USE PATH	LIGHTING	US 14 & LUCAS ROAD	US 14 & RIDGEFIELD ROAD SOUTH	US 14 & IL 176	US 14 & WOODSTOCK STREET	US 14 & CRYSTAL LAKE AVE	EMERGENCY VEHICLE PROTECTION/ILLUMINATED STREET NAME SIGNS	INTERCONNECT	100% STATE	100% CRYSTAL LAKE	
				100% STATE	MCHENRY COUNTY COLLEGE 100%	80% STATE 20% MCHENRY COUNTY	100% STATE	MCHENRY COUNTY COLLEGE 100%	93.3% STATE 6.7% MCHENRY COUNTY	100% STATE	90% STATE 10% CRYSTAL LAKE	90% STATE 10% CRYSTAL LAKE	100% CRYSTAL LAKE	100% STATE	100% STATE	100% CRYSTAL LAKE	
				0003	0003	0028	0021	0021	0021	0021	0021	0021	0021	0021	0043	0043	
50105220	PIPE CULVERT REMOVAL	FOOT	1,576	1,576													
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4	4													
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	14	14													
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1													
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1													
54214713	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 18"	EACH	7	7													
54214719	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 24"	EACH	5	5													
54214722	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 27"	EACH	4	4													
54214725	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 30"	EACH	2	2													
54214731	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 36"	EACH	1	1													
54215547	METAL END SECTIONS 12"	EACH	1	1													
5421A012	PIPE CULVERTS, CLASS A, TYPE 1 12" (TEMPORARY)	FOOT	24	24													
5421A024	PIPE CULVERTS, CLASS A, TYPE 1 24" (TEMPORARY)	FOOT	53	53													
5421D012	PIPE CULVERTS, CLASS D, TYPE 1 12" (TEMPORARY)	FOOT	27	27													
5421D015	PIPE CULVERTS, CLASS D, TYPE 1 15" (TEMPORARY)	FOOT	146	146													

* SPECIALTY ITEM