

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE ROADWAY
				0005 URBAN
25200110	SODDING, SALT TOLERANT	SQ YD	24	24
25200200	SUPPLEMENTAL WATERING	UNIT	1	1
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	7	7
40600537	LEVELING BINDER (HAND METHOD), IL-9.5FG, N70	TON	11	11
40600637	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N70	TON	999	999
40600990	TEMPORARY RAMP	SQ YD	234	234
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1999	1999
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	195	195
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	225	225
42400800	DETECTABLE WARNINGS	SQ FT	36	36
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	25340	25340
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	35	35
44000600	SIDEWALK REMOVAL	SQ FT	225	225
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	243	243

△ SPECIALTY ITEMS

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\p\dac\duncanbd\dms24419.EDD	104-shr-500.dgn	DRAWN -	REVISED -		379	118RS-3	KENDALL	19	3				
PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -	SCALE:		SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO. 66473				
PLOT DATE = 6/4/2014	DATE -	REVISED -	ILLINOIS FED. AID PROJECT										