

TEMPORARY INFORMATION SIGNING

NOTES:

- 1. USE 6" D BLACK LETTERING ON FLOURESENT ORANGE BACKGROUND.
- ERECT SIGNS AT LOCATIONS IN ADVANCE OF THE "ROAD CONSTRUCTION AHEAD" SIGNS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN() WITH INSTALLED PANEL (2) A MINIMUM OF ONE WEEK PRIOR TO THE START OF THE LANE CLOSURE.
- 4. REMOVE PANEL 2 ON THAT DATE.
- 5. SEE SPECIAL PROVISION "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. WILL BE PAID FOR PER SO FT AS "TEMPORARY INFORMATION SIGNING". EACH SIGN = 21 SO FT AND THE DATE PANEL ② WILL NOT BE MEASURED SEPARATELY FOR PAYMENT.

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -			DETAILS		F.A.U.	SECTION	COUNTY TO	TOTAL SHEET
c:\pw_work\pwidot\duncanbd\dms84419\ED0	6104-sht-details.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS		DETAILO		379	118RS-3	KENDALL	19 17
	PLOT SCALE = 100.0000 '/ in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION				0.0	110.10	CONTRACT N	NO. 66473
	PLOT DATE = 6/4/2014	DATE -	REVISED -		SCALE:	SHEET NO. 1 OF 2 SHEETS STA.	TO STA.		ILLINOIS FED. A	ID PROJECT	