

100% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				ROADWAY	RURAL
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	318	318	
20400800	FURNISHED EXCAVATION	CU YD	245	245	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	15	15	
40600527	LEVELING BINDER (HAND METHOD), IL-9.5FG, N50	TON	25	25	
40600627	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N50	TON	2110	2110	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600990	TEMPORARY RAMP	SQ YD	115	115	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	4329	4329	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	240	240	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	44345	44345	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	368	368	
48203017	HOT-MIX ASPHALT SHOULDERS, 5"	SQ YD	7072	7072	
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	12	12	
63200310	GUARDRAIL REMOVAL	FOOT	600	600	

*Specialty Items

FILE NAME *	USER NAME * #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		P.A.E. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -				697	17RS-4	FORD	11	5
		CHECKED -	REVISED -		SCALE: _____ SHEET NO. _____ OF _____ SHEETS STA. _____ TO STA. _____		CONTRACT NO. 66500		ILLINOIS FED. AID PROJECT		
		DATE -	REVISED -								