

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				100% STATE ROADWAY	100% STATE BOX CULVERT	100% STATE BOX CULVERT	100% STATE PIPE CULVERT
				0004 RURAL	0011 PR SN 038-2021	0011 PR SN 038-2020	0011 PR SN 038-2019
28100105	STONE RIPRAP, CLASS A3	SO YD	19	19			
28100107	STONE RIPRAP, CLASS A4	SO YD	332		124	100	108
28200200	FILTER FABRIC	SO YD	332		124	100	108
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SO YD	5612	5612			
31101900	SUBBASE GRANULAR MATERIAL, TYPE C	TON	518	518			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	38	38			
40600545	LEVELING BINDER (HAND METHOD), N90	TON	62	62			
<del>40600895</del>	<del>CONSTRUCTING TEST STRIP</del>	<del>EACH</del>	<del>2</del>	<del>2</del>			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	970	970			
40600990	TEMPORARY RAMP	SO YD	257	257			
40603243	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90	TON	43265	43265			
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	12015	12015			
44000100	PAVEMENT REMOVAL	SO YD	6056	6056			
44000300	CURB REMOVAL	FOOT	660	660			

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\p\work\p\100\100\duncanbd\dms30300\ap5005-shc-500.dgn		DRAWN -	REVISED -					57	*	ILLINOIS	190	4
PLOT SCALE = 100.0000 / 1"		CHECKED -	REVISED -		* (38-4)RS-2, (38-4)BR, BR1, BR3			CONTRACT NO. 66757				
PLOT DATE = 8/2/2014		DATE -	REVISED -		SCALE:	SHEET NO. 2 OF 9 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			