

SEEDING SCHEDULE								
LOCATION		SIDE	SEEDING	FURN	EROSION	NIT	PHOS	POT
			CL 2	EXC	CONTROL	FERT	FERT	FERT
			ACRE	CU YD	BLANKET	NUT	NUT	NUT
					SQ YD	LB	LB	LB
HERSCHER ROAD	958+00	RT	0.01	2.9	52	0.9	0.9	0.9
N 11000W ROAD	983+47	LT	0.01	2.9	52	0.9	0.9	0.9
S 11000W ROAD	1011+50	RT	0.01	2.9	52	0.9	0.9	0.9
N 10000W ROAD	1036+58	LT	0.01	2.9	52	0.9	0.9	0.9
S 10000W ROAD	1065+25	RT	0.01	2.9	52	0.9	0.9	0.9
BONFIELD ROAD	1089+31	LT	0.01	2.9	52	0.9	0.9	0.9
S 9000W ROAD	1118+65	RT	0.01	2.9	52	0.9	0.9	0.9
N 8000W ROAD	1142+39	LT	0.01	2.9	52	0.9	0.9	0.9
S 8000W ROAD	1173+75	RT	0.01	2.9	52	0.9	0.9	0.9
N 7000W ROAD	1195+80	LT	0.01	2.9	52	0.9	0.9	0.9
S 7000W ROAD	1213+38	RT	0.01	2.9	52	0.9	0.9	0.9
N 6000W ROAD	1249+05	LT	0.01	2.9	52	0.9	0.9	0.9
S 6000W ROAD	1266+34	RT	0.01	2.9	52	0.9	0.9	0.9
N 5620W ROAD	1269+19	LT	0.01	2.9	52	0.9	0.9	0.9
PROJECT TOTAL			0.14	40.6	728	12.6	12.6	12.6

RESURFACING SCHEDULE										
LOCATION	LENGTH	PVMT AREA	HMA SURF CSE	LEVEL BINDER (MM)	HMA SURF REM 2 1/4"	TEMP RAMP	BIT MAT (PR CT)	MIX FOR CRACKS, JOINTS & FLGWYS	LEVEL BINDER (HM)	AGG SHLD
957+38 TO 965+36.62	798.62	2662.1	223.6	111.8	2662.1	50	1797	0.8	1.3	37.9
965+36.62 TO 966+32.38 (OMISSION)	95.76									
966+32.38 TO 1208+30	24197.62	80658.7	6775.3	3387.7	80658.7	25	54445	24.2	40.3	1148.3
1208+30 TO 1221+40	1310	5566.7	467.6	233.8	5566.7		3758	1.7	2.8	62.2
1221+40 TO 1296+00	7460	24866.7	2088.8	1044.4	24866.7		16785	7.5	12.4	354
1296+00 TO 1308+56	1256	17386.7	1460.5	730.2	17386.7	25	11736	5.2	8.7	59.6
TOTAL			11015.8	5507.9	131140.9	100	88521	39.4	65.5	1662.0

PAVEMENT MARKING SCHEDULE															
LOCATION	LENGTH	POLYUREA PAVEMENT MARKING, TY 1 4"		POLYUREA PVMT MARK TYPE 1 8"		POLYUREA PAVEMENT MARKING, TY 1 12"		POLYUREA PVMT MARK TYPE 1 24"		POLYUREA PVMT MARK TYPE 1 LETTERS & SYMB	RAISED REFLECT PVMT MARK REM	RAISED REFLECT PVMT MARK	PRISMATIC CURB REFLECT	SHORT TERM PVMT MARK	WORK ZONE PVMT MARK REM
		WHITE	YELLOW	WHITE	WHITE	YELLOW	WHITE								
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT								
957+38 TO 1208+30	25092	100368	1000	12546						314	314			7528	836
1208+30 TO 1221+40	1310	2618	4646	98	354			31.2		68	68			1436.4	159
1221+40 TO 1296+00	7460	29840	2000	3730						93	93			2238	248
1296+00 TO 1306+56	1095	2710	4587	443	60	280	56	92.4		65	65	8		1183.2	131
SUBTOTAL		135536	12233	16817	60	634	56	123.6		540	540	8		12385.6	1374
PROJECT TOTAL		147769		16817	694		56	123.6		540	540	8		12385.6	1374

TEMPORARY PAVEMENT MARKING SCHEDULE									
LOCATION	LENGTH	TEMPORARY PAVEMENT MARKING 4"		TEMP PVMT MARK 6"	TEMP PVMT MARK 8"	TEMPORARY PAVEMENT MARKING 12"		TEMP PVMT MARK 24"	TEMP PVMT MARK LETTERS & SYMB
		WHITE	YELLOW	YELLOW	WHITE	WHITE	YELLOW	WHITE	
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	
957+38 TO 1208+30	25092	100368	1000	6273					
1208+30 TO 1221+40	1310	2618	4646	98		354		31.2	
1221+40 TO 1296+00	7460	29840	2000	1865					
1296+00 TO 1308+56	1095	2710	4587	443	60	280	56	92.4	
SUBTOTAL		135536	12233	8138	541	60	634	56	123.6
PROJECT TOTAL		147769		8138	541	694		56	123.6