

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE ROADWAY
				0005
				RURAL
20400800	FURNISHED EXCAVATION	CU YD	39	39
25100630	EROSION CONTROL BLANKET	SQ YD	223	223
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	35	35
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	7	7
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	93	93
40600990	TEMPORARY RAMP	SQ YD	75	75
40600527	LEVELING BINDER (HAND METHOD), IL-9.5FG, N50	TON	11	11
40600627	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N50	TON	889	889
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1752	1752
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	61	61
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	21288	21288
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	13348	13348
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1274	1274
67100100	MOBILIZATION	L SUM	1	1

FILE NAME :	USER NAME : duncanbd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\p1dot\duncanbd\0253031\036	018-shr-cover.dgn	DRAWN -	REVISED -		573	017RS-6	DEKALB	11	3				
	PLOT SCALE * 100.0000 ' / in.	CHECKED -	REVISED -						CONTRACT NO. 66B18				
	PLOT DATE * 5/6/2014	DATE -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT				