

CONSTRUCTION CODE

100% STATE

ROADWAY
0005
RURAL

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
20200100	EARTH EXCAVATION	CU YD	13	13
20400800	FURNISHED EXCAVATION	CU YD	32	32
25000110	SEEDING, CLASS 1A	ACRE	0.33	0.33
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	30	30
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	30	30
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	30	30
25100630	EROSION CONTROL BLANKET	SQ YD	1612	1612
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	57	57
40600990	TEMPORARY RAMP	SQ YD	592	592
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	15,558	15,558
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	895	895
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	1245	1245
42400800	DETECTABLE WARNINGS	SQ FT	260	260
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	174,545	174,545

FILE NAME #	USER NAME # Schwankerg	DESIGNED -	REVISED -
c:\pwork\pwidat\schwankerg\0287053	066805-shi-900.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 / / in.	CHECKED -	REVISED -
	PLOT DATE = 6/6/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
68	(101,102)RS-3	LIVINGSTON	22	3
			CONTRACT NO. 66885	
ILLINOIS FED. AID PROJECT				

Rev.