

MAINLINE PAVING SCHEDULE											
STA. TO STA.	LENGTH	MAINLINE		HMA	HMA SURF	LEV BIND	BIT MAT	MIX JTS	LEV BIND	AGG	TEMP
		WIDTH	AREA	SURF REM	CSE MIX C	(MM) IL-9.5FG	PRIME	CRACKS. & FLANGEWAYS	(HM) IL-9.5FG	WEDGE	RAMP
		FT	SQ YD	2 1/4"	N50	N50	COAT	FLANGEWAYS	N50	SHLDS B	SQ YD
796+06 - 800+83	477	52	2756.0	2756.0	231.50	115.75	1860.30	0.83	1.38	13.58	20.00
800+83 - 850+83	5000	32	17777.8	17777.8	1493.33	746.67	12000.00	5.33	8.89	142.36	
850+83 - 954+04	10322	32	36700.0	36700.0	3082.80	1541.40	24772.49	11.01	18.35	293.89	20.00
954+04 - 955+08	103	SN 006-0086 OMISSION									
955+08 - 1170+68	21560	32	76656.9	76656.9	6439.18	3219.59	51743.40	23.00	38.33	613.86	20.00
1170+68 - 1187+89	1721	46	8796.2	8796.2	738.88	369.44	5937.45	2.64	4.40	45.40	
1187+89 - 1242+06	5417	32	19260.4	19260.4	1617.88	808.94	13000.80	5.78	9.63	154.23	20.00
1242+06 - 1243+40	134	SN 006-0156 OMISSION									
1243+40 - 1266+13	2273	32	8081.8	8081.8	678.87	339.43	5455.20	2.42	4.04	64.72	40.00
1266+13 - 1267+38	125	SN 006-0157 OMISSION									
1267+38 - 1420+00	15262	32	54264.9	54264.9	4558.25	2279.13	36628.80	16.28	27.13	434.54	40.00
<b>TOTAL</b>			<b>224294.0</b>	<b>224294</b>	<b>18841</b>	<b>9420</b>	<b>151398</b>	<b>67</b>	<b>112</b>	<b>1763</b>	<b>160</b>

FOLDER 40-3					CONTRACT NO. 66C34		
ILL RTE 40					BUREAU CO.		
I-80 TO IL 92							
GPS POINT NUMBER OR INDEX NUMBER	DESCRIPTION			EXISTING MONUMENT TYPE	PROPOSED MONUMENT TYPE	MONUMENT RECORD TO BE RECORDED	RESPONSIBILITY
40022	NE COR SEC 9-16-7E			PLUG HOLE	TYPE 1	YES	1
40029	SW COR SEC 22-17-7E			PK NAIL	TYPE 1	YES	1
40030	E OTR COR SEC 21-17-7E			SURVEY NAIL	TYPE 1	YES	1
40031	SE COR SEC 16-17-7E			PK NAIL	TYPE 1	YES	1
40032	E OTR COR SEC 16-17-7E				TYPE 1	YES	1
40032A	NE COR OF SE OTR OF NE OTR SEC 16-17-7E IN GRAVEL SHOULDER. ONLY NEEDED IF ADDING ASPHALT SHOULDER			ROD	TYPE 1	YES	1
40034	W OTR COR SEC 10-17-7E			SURVEY NAIL	TYPE 1	YES	1
40035	NE COR SEC 9-17-7E				TYPE 1	YES	1
40039	E OTR COR SEC 33-18-7E				TYPE 1	YES	1
40039A	NE COR OF SE OTR OF NE OTR SEC 33-18-7E			PK NAIL	TYPE 1	YES	1
40040	SE COR SEC 28-18-7E			PK NAIL	TYPE 1	YES	1
40041	E OTR COR SEC 28-18-7E			PK NAIL	TYPE 1	YES	1
40042	SE COR SEC 21-18-7E			PK NAIL	TYPE 1	YES	1
40043	E OTR COR SEC 21-18-7E			PK NAIL	TYPE 1	YES	1
40044	NE COR SEC 21-18-7E			PK NAIL	TYPE 1	YES	1

THIS NOTE TO BE INCLUDED IN PLANS:  
LISTED MONUMENT LOCATIONS HAVE BEEN RECORDED BY GPS. PRE CONSTRUCTION TIES BY THE R.E. ARE NOT REQUIRED.  
IF AN UNLISTED MONUMENT IS FOUND, IT MUST BE TIED BY THE R.E. AND BROUGHT TO THE ATTENTION OF THE PLATS AND PLANS MANAGER.  
AFTER RESURFACING, THE R.E. IS TO CONTACT THE PLATS AND PLANS MANAGER TO ESTABLISH LOCATIONS FOR PERMANENT SURVEY MARKER CORING.

**RESPONSIBILITY:**  
1) RESIDENT TO RE-ESTABLISH MONUMENT (PAY ITEM REQUIRED. PERMANENT SURVEY MARKER, TYPE 1)  
2) PLATS AND PLANS TO RE-ESTABLISH MONUMENT

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pw\work\p1dot\duncanbd\0304146\0366C34-sht-schedule.dgn		DRAWN -	REVISED -		646	(103,104)RS-6	BUREAU	28	8				
PLOT SCALE = 100.0000' / 1in.		CHECKED -	REVISED -						<b>CONTRACT NO. 66C34</b>				
PLOT DATE = 6/6/2014		DATE -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			