

**CRACK ROUTING AND SEALING SCHEDULE - FAP 317 (US 24)**

LOCATION	CENTERLINE CRACK ROUTING (PAVEMENT)	* TRANSVERSE CRACK ROUTING (PAVEMENT)	CENTERLINE CRACK FILLING	* TRANSVERSE CRACK FILING	REMARKS
L.M. - L.M.	FOOT	FOOT	POUND	POUND	
L.M. 0.00					US RTE. 45 INTERSECTION
0.00 - 1.00	6180	864	2163	302	INCLUDES LEFT TURN LANE QUANTITY
L.M. 1.0					N 900 E RD
1.00 - 2.10	5808	950	2033	333	
2.10 - 2.13					BRIDGE OMISSION S.N. 038-0032
2.13 - 3.03	4752	778	1663	272	
3.03 - 3.10					BRIDGE OMISSION S.N. 038-0033
3.10 - 4.00	4752	778	1663	272	
4.00 - 4.05					BRIDGE OMISSION S.N. 038-0034
4.05 - 5.00	5016	821	1756	287	
L.M. 5.00					N 1300 E RD
5.00 - 6.00	5280	864	1848	302	
L.M. 6.00					IL RTE. 49 INTERSECTION
SUBTOTAL	31788	5054	11126	1768	
TOTAL		36842		12894	

**PAVEMENT MARKING SCHEDULE - FAP 317 (US 24)**

LOCATION	PAINT PAVEMENT MARKING LINE 6'' YELLOW	REMARKS
L.M. - L.M.	FOOT	
L.M. 0.00		US RTE. 45 INTERSECTION
0.08 - 6.00	7814	
L.M. 6.00		IL RTE. 49 INTERSECTION
TOTAL	7814	

\* ESTIMATING 36 FULL WIDTH (24')  
TRANSVERSE CRACKS PER MILE.  
FINAL QUANTITIES WILL BE DETERMINED  
BY THE RE/RT UPON CONSTRUCTION.