

IL 71 PAVEMENT SCHEDULE

			PVMT WIDTH	LEVELING BINDER (MM), N50	HMA SURF. CSE. MIX C, N50	AGG. SHOULDER TYPE B	TEMP. RAMP	RRPM EACH	RRPM EACH	HMA SURF. REM. 2 1/4"	MIX FOR CRACKS, JTS FLGWYS	BIT PRIME COAT
			LENGTH	TON	TON	TON	SQ YD	EACH	EACH	SQ YD	TON	LBS
START PROJECT	2+25.00 (225' EAST OF IL 89) TO 50+24.00	4799	26	582.3	1164.6	547	22	60	60	13863.8	4.2	9358
	50+24.00 TO 80+88.00	3064	26	371.8	743.5			38	38	8851.6	2.7	5975
	80+88.00 TO 107+52.00 (COUNTY BOUNDARY)	2664	26	323.2	646.5	303		33	33	7696	2.3	5195
END PROJECT	107+52.00 TO 204+41.50 (WEST END SN 050-0124)	9689.5	26	1175.7	2351.3	1104	22	121	121	27991.9	8.4	18895
GRAND TOTAL		20216.5		2453	4906	1954	44	252	252	58403	17.5	39423

IL 71 PAVEMENT MARKING SCHEDULE

				PAINT PVT MARK. 4" WHITE*	PAINT PVT MARK. 4" YELLOW*	PAINT PVT MARK. 6" YELLOW*	SHORT-TERM PAVEMENT MARKING	TEMPORARY PVT. MARK. REMOVAL
LOCATION	COMMENT	LENGTH	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT
START PROJECT	2+25 TO 11+00	SKIP	875	3500		438	263	88
	11+00 TO 18+00	EB NO PASS, WB PASS	700	2800	1400	350	210	70
	18+00 TO 21+00	SKIP	300	1200		150	90	30
	21+00 TO 22+70	WB NO PASS, EB PASS	170	680	340	85	51	17
	22+70 TO 35+00	SKIP	1230	4920		615	369	123
	35+00 TO 42+00	EB NO PASS, WB PASS	700	2800	1400	350	210	70
	42+00 TO 43+25	SKIP	125	500		63	38	13
	43+25 TO 51+50	WB NO PASS, EB PASS	825	3300	1650	413	248	83
	51+50 TO 96+50	SKIP	4500	18000		2250	1350	450
	96+50 TO 107+25	EB NO PASS, WB PASS	1075	4300	2150	538	323	108
CO. BOUNDARY	107+25 TO 107+52	DOUBLE NO PASS	27	108	108		8	3
	107+52 TO 115+00	DOUBLE NO PASS	748	2992	2992		224	75
	115+00 TO 126+50	WB NO PASS, EB PASS	1150	4600	2300	575	345	115
	126+50 TO 174+75	SKIP	4825	19300		2413	1448	483
	174+75 TO 184+00	EB NO PASS, WB PASS	925	3700	1850	463	278	93
END PROJECT	184+00 TO 204+41.5	DOUBLE NO PASS	2041.5	8166	8166		612	204
GRAND TOTAL			20216.5	80866	22356	8703	6065	2022

*NOTE: ALL PAINT PAVEMENT MARKING QUANTITIES HAVE BEEN DOUBLED BASED ON TWO APPLICATIONS