

APPROX. LOCATION	CLASS D PATCHES			
	TYPE III, 13"		TYPE IV, 13"	
	EASTBOUND	WESTBOUND	EASTBOUND	WESTBOUND
	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.
STA. 465+00 IN OVERLAY SECTION	16	16		
BETWEEN WASHINGTON ST. TO UNION ST.	15	15		
	15	15		
BETWEEN MAPLE ST. TO LYNN ST.	15	15		
STA. 510+00 IN OVERLAY SECTION		15		
STA. 513+00			30	
STA. 514+67			50	50
STA. 538+00				27
STA. 542+00		22	33	
STA. 569+00			60	60
STA. 604+50			26	26
STA. 605+50	16	16		
STA. 609+00			32	
STA. 611+50 TO 611+83			37	37
STA. 612+58 TO 613+13			60	60
STA. 614+00 TO 615+00		22		
STA. 618+00			53	
STA. 626+50 TO 627+32*			120	120
SUB-TOTAL	92	137	501	380
<b>GRAND TOTAL</b>	<b>229</b>		<b>881</b>	

\* SEE UNDERDRAINS, GUTTER OUTLETS AND RELATED ITEMS SCHEDULE

PAINT PAVEMENT MARKINGS				
APPROX. LOCATION		4" LINE		
		YELLOW NO PASSING	YELLOW SKIP-DASH	WHITE EDGE LINE
		FOOT	FOOT	FOOT
461+40 TO 488+00	CL		665	
461+40 TO 488+61.57	LT			2719.7
462+93.77 TO 473+66.54	RT			1072.78
474+46.54 TO 477+53.86	RT			300.85
507+08.43 TO 536+58.59	RT			2950.17
507+13.51 TO 510+43.79	LT			330.27
511+03.82 TO 588+73.69	LT			7769.87
518+00 TO 553+76.31	CL		894.1	
537+44.54 TO 563+04.09	RT			2559.55
543+53.84 TO 555+77.39	EB	1223.6		
553+76.31 TO 565+84.71	WB	1208.4		
555+77.39 TO 578+00	CL		555.7	
563+85.33 TO 589+19.85	RT			2534.32
578+00 TO 589+39.95	CL		285	
580+08.67 TO 590+58.43	EB	1049.8		
589+39.95 TO 598+92.88	WB	952.9		
590+40.43 TO 641+50	LT			5109.57
590+58.43 TO 608+00	CL		435.4	
590+92.56 TO 641+50	RT			5057.44
608+00 TO 641+50	CL		837.5	
627+69.02 TO 641+50	EB	1380.98		
SUB-TOTAL		5816	3673	30405
<b>GRAND TOTAL</b>			<b>39893</b>	

NOTE: FINAL LIMITS TO BE DETERMINED BY THE RESIDENT ENGINEER

UNDERDRAINS, GUTTER OUTLETS AND RELATED ITEMS				
PAY ITEM DESCRIPTION	UNIT	STA. 626+50 TO STA. 627+32	STA. 611+00	TOTAL QUANTITY
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU. YD.	80		80
REMOVING INLETS	EACH	2		2
GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ. YD.	265		265
SUB-BASE GRANULAR MATERIAL, TYPE B, 12"	SQ. YD.	240		240
PIPE UNDERDRAINS 6"	FOOT	28		28
PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	20		20
CONCRETE HEADWALL FOR PIPE DRAINS	EACH	2		2
STONE RIPRAP, CLASS B3	SQ. YD.	54	54	108
FILTER FABRIC (FOR USE WITH RIPRAP)	SQ. YD.	54	54	108

SHORT TERM PAVEMENT MARKING				WORK ZONE PAVEMENT MARKING REMOVAL
LOCATION- ONLY THE AREAS BEING RESURFACED	LOCATION	YELLOW SKIP-DASH	WHITE EDGE LINE	
		FOOT	FOOT	
STA. 461+00 (EXISTING BUTT JOINT) TO 475+50	1450	145	116	87
STA. 507+05 (LYNN ST.) TO STA. 511+25 (NELSON ST.) EXISTING V-GUTTER ON SOUTH SIDE	420	42		14
STA. 542+80 TO 568+15 (LIMITS OF EX. V-GUTTER)	2535	253.5		84
STA. 571+00 TO 576+00	500	50		17
STA. 581+00 TO 589+00	800	80		27
STA. 598+85 TO 602+50 (WITHIN V-GUTTER SECTION)	365	36.5		12
STA. 620+00 TO 622+00	200	20		7
STA. 627+00 TO 633+50 (V-GUTTER SECTION)	650	65		22
SUB-TOTAL		692	116	
3 APPLICATIONS		2076	348	
<b>GRAND TOTAL</b>		<b>2424</b>		<b>269</b>

FILE NAME = D468898-typicals.dgn	USER NAME = aubreys	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -
Default	PLOT DATE = 5/16/2014	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.S. RTE. 379	SECTION (101, 111)RS-3	COUNTY KNOX	TOTAL SHEETS 33	SHEET NO. 5
ILLINOIS FED. AID PROJECT				CONTRACT NO. 68B98