

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	HENDERSON COUNTY ROADWAY 0005 100% STATE	WARREN COUNTY ROADWAY 0005 100% STATE
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	30,007	14,413	15,594
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	33	11	22
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	7	3	4
40600285	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	POUND	13,504	6,486	7,018
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1,283	616	667
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	2	1	1
67100100	MOBILIZATION	LSUM	1	0.5	0.5
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	LSUM	1	0.5	0.5
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	5	5
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	101,562	49,248	52,314
X0327301	RELOCATE EXISTING MAILBOX	EACH	6	3	3
X4404400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	30,007	14,413	15,594

*

* SPECIALTY ITEM

△ REVISED 7-21-14

FILE NAME : 68C07 - IL 116 Henderson and Warren.dgn	USER NAME : aubrugg	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 665	SECTION 137W-1; 138, 139W-2	COUNTY HENDERSON/WARREN	TOTAL SHEETS 15	SHEET NO. 3
Default	PLOT SCALE : 100.0000' / 1"	CHECKED -	REVISED -		NOT TO SCALE					
	PLOT DATE : 5/21/2014	DATE -	REVISED -		SHEET 1	OF 1	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT
CONTRACT NO. 68C07										

SCHEDULE OF HMA WIDENING QUANTITIES (CONTINUED)

	OMISSION NOTES	LENGTH	AREA	AGGREGATE WEDGE SHOULDER, TY B	HMA BASE CSE WIDENING, 9"	PAVEMENT REMOVAL (SPECIAL)	POLYMERIZED BIT. MAT. (PRIME COAT)
		FEET	SQ YD	TON	SQ YD	SQ YD	POUND
WARREN COUNTY							
LT. STA. 469+79.52 TO 474+00.92	GUTTER						
LT. STA. 474+00.92 TO 494+13.26		2,012.34	670.78	28.68	670.78	670.78	301.85
LT. STA. 494+13.26 TO 495+31.01	GUTTER						
LT. STA. 495+31.01 TO 496+00.57		69.56	23.19	0.99	23.19	23.19	10.43
LT. STA. 496+00.57 TO 496+73.31	5TH ST.						
LT. STA. 496+73.31 TO 549+00.02		5,226.71	1,742.24	74.48	1,742.24	1,742.24	784.01
LT. STA. 549+00.02 TO 549+52.26	15TH ST.						
LT. STA. 549+52.26 TO 566+39.03		1,686.77	562.26	24.04	562.26	562.26	253.02
LT. STA. 566+39.03 TO 570+96.43	GUTTER						
LT. STA. 570+96.43 TO 574+48.84		352.41	117.47	5.02	117.47	117.47	52.86
LT. STA. 574+48.84 TO 586+58.85	STRUCTURE						
LT. STA. 586+58.85 TO 604+57.23		1,798.38	599.46	25.63	599.46	599.46	269.76
LT. STA. 604+57.23 TO 605+13.25	26TH ST.						
LT. STA. 605+13.25 TO 628+81.93		2,368.68	789.56	33.75	789.56	789.56	355.30
LT. STA. 628+81.93 TO 629+36.80	30TH ST.						
LT. STA. 629+36.80 TO 682+26.10		5,289.30	1,763.10	75.37	1,763.10	1,763.10	793.40
LT. STA. 682+26.10 TO 682+85.59	40TH ST.						
LT. STA. 682+85.59 TO 731+36.59		4,851.00	1,617.00	69.13	1,617.00	1,617.00	727.65
SUB-TOTAL:				337.09	7,885.05	7,885.05	3,548.27

△ REVISED 7-21-14

SCHEDULE OF HMA WIDENING QUANTITIES (CONTINUED)								
	OMISSION NOTES	LENGTH	AREA	AGGREGATE WEDGE SHOULDER, TY B	HMA BASE CSE WIDENING, 9"	PAVEMENT REMOVAL (SPECIAL)	POLYMERIZED BIT. MAT. (PRIME COAT)	
		FEET	SQ YD	TON	SQ YD	SQ YD	POUND	
WARREN COUNTY (CONTINUED)								
RT. STA. 469+79.52 TO 474+00.92	GUTTER							
RT. STA. 474+00.92 TO 496+02.19		2,201.27	733.76	31.37	733.76	733.76	330.19	
RT. STA. 496+02.19 TO 496+61.05	5TH ST.							
RT. STA. 496+61.05 TO 522+63.53		2,602.48	867.49	37.09	867.49	867.49	390.37	
RT. STA. 522+63.53 TO 522+97.19	10TH ST.							
RT. STA. 522+97.19 TO 548+75.83		2,578.64	859.55	36.75	859.55	859.55	386.80	
RT. STA. 548+75.83 TO 549+45.21	15TH ST.							
RT. STA. 549+45.21 TO 566+00.71		1,655.50	551.83	23.59	551.83	551.83	248.33	
RT. STA. 566+00.71 TO 574+52.73	GUTTER							
RT. STA. 574+52.73 TO 580+72.55	STRUCTURE							
RT. STA. 580+72.55 TO 586+50.09	GUTTER							
RT. STA. 586+50.09 TO 588+89.01		238.92	79.64	3.40	79.64	79.64	35.84	
RT. STA. 588+89.01 TO 589+36.83	22ND ST.							
RT. STA. 589+36.83 TO 628+82.19		3,945.36	1,315.12	56.22	1,315.12	1,315.12	591.80	
RT. STA. 628+82.19 TO 629+37.68	30TH ST.							
RT. STA. 629+37.68 TO 631+75.77	GUTTER							
RT. STA. 631+75.77 TO 682+24.16		5,048.39	1,682.80	71.94	1,682.80	1,682.80	757.26	
RT. STA. 682+24.16 TO 682+79.44	40TH ST.							
RT. STA. 682+79.44 TO 731+36.59		4,857.15	1,619.05	69.21	1,619.05	1,619.05	728.57	
SUB-TOTAL:					329.57	7,709.24	7,709.24	3,469.16
WARREN COUNTY TOTAL:					667	15,594	15,594	7,018
TOTAL:					1,283	30,007	30,007	13,504



△ REVISED 7-21-14