

SCHEDULE OF QUANTITIES

FAI-55 & FAI-74 INTERCHANGE

CLASS B PATCHING SCHEDULE, 10" (I-55 & I-74 INTERCHANGE RAMPS)

LOCATION	STATION	LENGTH (FT)	WIDTH (FT)	44200970 TYPE II, 10" (SQ YD)	44201299 DOWEL BARS, 1 1/2" (EACH)	44213200 SAW CUTS (FT)	44213204 TIE BARS 3/4" (EACH)
RT. RAMP E	4+50.00	6.00	8.00	5.33	14.00	42.00	
RT. RAMP E	37+30.00	6.00	8.00	5.33	14.00	42.00	
RT. RAMP E	37+60.00	6.00	8.00	5.33	14.00	42.00	
RT. RAMP E	38+00.00	6.00	8.00	5.33	14.00	42.00	
RT. RAMP E	38+25.00	6.00	8.00	5.33	14.00	42.00	
RT. RAMP E	38+60.00	6.00	8.00	5.33	14.00	42.00	
RT. RAMP E	39+00.00	6.00	8.00	5.33	14.00	42.00	
RT. RAMP E	40+00.00	6.00	8.00	5.33	14.00	42.00	
RT. MISC	MISC	6.00	8.00	5.33	14.00	42.00	
RT. MISC	MISC	6.00	8.00	5.33	14.00	42.00	
LT. RAMP E	4+50.00	6.00	8.00	5.33	14.00	42.00	3.00
LT. RAMP E	37+30.00	6.00	8.00	5.33	14.00	42.00	3.00
LT. RAMP E	37+60.00	6.00	8.00	5.33	14.00	42.00	3.00
LT. RAMP E	38+00.00	6.00	8.00	5.33	14.00	42.00	3.00
LT. RAMP E	38+25.00	6.00	8.00	5.33	14.00	42.00	3.00
LT. RAMP E	38+60.00	6.00	8.00	5.33	14.00	42.00	3.00
LT. RAMP E	39+00.00	6.00	8.00	5.33	14.00	42.00	3.00
LT. RAMP E	40+00.00	6.00	8.00	5.33	14.00	42.00	3.00
LT. MISC	MISC	6.00	8.00	5.33	14.00	42.00	3.00
LT. MISC	MISC	6.00	8.00	5.33	14.00	42.00	3.00
RT. RAMP F	4+80.00	6.00	8.00	5.33	14.00	42.00	
RT. RAMP F	24+00.00	6.00	8.00	5.33	14.00	42.00	
RT. RAMP F	24+15.00	6.00	8.00	5.33	14.00	42.00	
RT. RAMP F	24+30.00	6.00	8.00	5.33	14.00	42.00	
RT. RAMP F	24+45.00	6.00	8.00	5.33	14.00	42.00	
RT. RAMP F	24+60.00	6.00	8.00	5.33	14.00	42.00	
RT. RAMP F	25+50.00	15.00	8.00	13.33	14.00	69.00	9.00
RT. MISC	MISC	6.00	8.00	5.33	14.00	42.00	
RT. MISC	MISC	6.00	8.00	5.33	14.00	42.00	
LT. RAMP F	4+80.00	6.00	8.00	5.33	14.00	42.00	3.00
LT. RAMP F	24+00.00	6.00	8.00	5.33	14.00	42.00	3.00
LT. RAMP F	24+15.00	6.00	8.00	5.33	14.00	42.00	3.00
LT. RAMP F	24+30.00	6.00	8.00	5.33	14.00	42.00	3.00
LT. RAMP F	24+45.00	6.00	8.00	5.33	14.00	42.00	3.00
LT. RAMP F	24+60.00	6.00	8.00	5.33	14.00	42.00	3.00
LT. RAMP F	25+50.00	15.00	8.00	13.33	14.00	69.00	18.00
LT. MISC	MISC	6.00	8.00	5.33	14.00	42.00	3.00
LT. MISC	MISC	6.00	8.00	5.33	14.00	42.00	3.00
TOTAL =				218.54	532.00	1650.00	81.00
USE =				220.00	532.00	1650.00	81.00
				(SQ YD)	(EACH)	(FT)	(EACH)

NOTES:
THE STATIONS LISTED FOR THE PATCHES ARE APPROXIMATE LOCATIONS. THE ACTUAL LOCATION AND SIZE SHALL BE FIELD VERIFIED AS SPECIFIED IN G.N.-442B.
PATCHING ON THE RAMPS SHALL BE CONSTRUCTED IN HALF LANE WIDTHS. SEE CLASS B PATCHING SPECIAL PROVISION FOR TIE BAR REQUIREMENTS.

CLASS B PATCHING SCHEDULE, 12" (I-55 N.B. RT. LANE ONLY)

LOCATION	STATION	LENGTH (FT)	WIDTH (FT)	44200994 TYPE II, 12" (SQ YD)	44200998 TYPE III, 12" (SQ YD)	44201000 TYPE IV, 12" (SQ YD)	44201299 DOWEL BARS, 1 1/2" (EACH)	44213200 SAW CUTS (FT)	44213204 TIE BARS 3/4" (EACH)	44213100 PAVEMENT FABRIC (SQ YD)
N.B. RT. LANE	277+50.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	277+00.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	275+00.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	274+00.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	273+75.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	272+80.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	272+50.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	272+00.00	30.00	12.00			40.00	30.00	126.00	30.00	40.00
N.B. RT. LANE	271+80.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	271+30.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	270+80.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	270+40.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	269+90.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	269+75.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	269+30.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	268+75.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	267+00.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	266+50.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	266+00.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	265+50.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	265+00.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	262+00.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	261+50.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	261+00.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	260+50.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	260+00.00	6.00	12.00	8.00			20.00	54.00		
N.B. RT. LANE	MISC	12.00	12.00			16.00	20.00	72.00		16.00
N.B. RT. LANE	MISC	12.00	12.00			16.00	20.00	72.00		16.00
TOTAL =				200.00	32.00	40.00	570.00	1620.00	30.00	72.00
USE =				200.00	35.00	40.00	570.00	1620.00	30.00	75.00
				(SQ YD)	(SQ YD)	(SQ YD)	(EACH)	(FT)	(EACH)	(SQ YD)

NOTES:
THE STATIONS LISTED FOR THE PATCHES ARE APPROXIMATE LOCATIONS. THE ACTUAL LOCATION AND SIZE SHALL BE FIELD VERIFIED AS SPECIFIED IN G.N.-442B.
PATCHING ON I-55 N.B. SHALL BE CONSTRUCTED IN FULL LANE WIDTHS.

78009004 MODIFIED URETHANE PAVEMENT MARKING - LINE 4"

LOCATION	STATION	TO	STATION	LENGTH (FT)	COLOR
RT. RAMP C	3+00.00		42+50.00	3950.00	WHITE
LT. RAMP C	3+00.00		42+50.00	3950.00	YELLOW
RT. RAMP E	37+00.00		40+00.00	300.00	WHITE
LT. RAMP E	37+00.00		40+00.00	300.00	YELLOW
RT. RAMP F	24+00.00		26+00.00	200.00	WHITE
LT. RAMP F	24+00.00		26+00.00	200.00	YELLOW
RT. I-55 N.B.	260+00.00		278+00.00	1800.00	WHITE
MISC	MISC			500.00	WHITE
TOTAL =				11200.00	
				FT	