



TYPICAL SECTION AT MAILBOX TURNOUT

NOTE: SEE STANDARD 406201 FOR MAILBOX TURNOUT DETAILS

NOTES

THE COST OF THE ASPHALT MATERIALS, AND AGGREGATE (PRIME COAT) FOR ENTRANCES AND PUBLIC ROADS AND APPROACHES SHALL BE INCLUDED IN THE PAY ITEM INCIDENTAL HOT-MIX ASPHALT SURFACING.

THE COST OF EXCAVATION IS INCLUDED IN THE PAY ITEM INCIDENTAL HOT-MIX ASPHALT SURFACING.

IF THERE IS NOT EXISTING HOT-MIX ASPHALT SHOULDER THEN THE ENTRANCE TAPER STARTS AT THE EDGE OF EXISTING PAVEMENT.

THE COST OF THE BITUMINOUS MATERIALS AND AGGREGATE (PRIME COAT) FOR ENTRANCES AND PUBLIC ROAD APPROACHES SHALL BE INCLUDED IN THE PAY ITEM INCIDENTAL HOT-MIX ASPHALT SURFACING.

SIDE	STATION	TYPE	INCIDENTAL HOT-MIX ASPHALT SURFACING	
			TON	TON
LT	1116+40	PRA	1.7	
RT	1119+04	PRA	2.5	
RT	1127+58	FE		2.1
LT	1131+36	FE		0.0
LT	1135+45	FE		0.0
RT	1148+82	FE		0.0
LT	1169+04	FE		0.9
RT	1177+41	PE	1.4	
LT	1182+23	FE		1.2
RT	1185+62	PRA	3.0	
RT	1191+50	PRA	1.3	
RT	1195+63	MBT		2.0
LT	1195+79	PE	1.4	
RT	1198+95	MBT		2.0
RT	1199+12	PE	1.7	
RT	1205+65	FE		0.9
LT	1217+48	FE		1.6
RT	1225+22	PRA	2.5	
LT	1225+63	FE		1.1
LT	1237+98	PRA	2.6	
RT	1238+41	FE		0.9

SIDE	STATION	TYPE	INCIDENTAL HOT-MIX ASPHALT SURFACING	
			TON	TON
RT	1251+78	PRA	2.7	
LT	1263+20	FE		1.2
RT	1263+81	FE		0.9
LT	1272+23	PE	1.3	
RT	1272+23	MBT		2.0
LT	1278+28	FE		0.9
RT	1284+78	PRA	2.5	
LT	1291+48	PRA	3.5	1.6
RT	1297+49	FE		1.6
LT	1307+23	PE	1.4	
LT	1307+30	MBT		2.0
LT	1307+90	FE		1.3
LT	1317+65	PE	1.4	
LT	1317+85	MBT		1.6
RT	1328+33	FE		1.5
RT	1338+67	FE		1.2
LT	1338+67	PRA	2.1	
RT	1344+25	PRA	2.3	
RT	1351+15	FE		0.9
LT	1351+83	FE		1.8
RT	1357+63	FE		2.0

SIDE	STATION	TYPE	INCIDENTAL HOT-MIX ASPHALT SURFACING	
			TON	TON
LT	1359+47	MBT		1.6
LT	1359+63	PE		1.6
RT	1364+30	FE		1.2
LT	1366+32	FE		0.9
RT	1376+10	PE		0.0
LT	1376+14	MBT		1.6
LT	1379+19	FE		0.0
LT	1379+25	MBT		1.6
LT	1379+45	PE		0.0
LT	1380+69	PE		0.0
LT	1382+94	FE		0.0
RT	1383+68	CE	0.0	
RT	1397+49	FE		0.0
LT	1405+77	FE		1.5
RT	1412+45	PE	1.4	
LT	1412+57	MBT		2.0
TOTALS			103.	134.6

SIDE	STATION	TYPE	INCIDENTAL HOT-MIX ASPHALT SURFACING	
			TON	TON

SIDE	STATION	TYPE	INCIDENTAL HOT-MIX ASPHALT SURFACING	
			TON	TON

FE=FIELD ENTRANCE PRA - PUBLIC ROAD APPROACH
PE=PRIVATE ENTRANCE MBT - MAILBOX TURNOUT
CE=COMMERCIAL ENTRANCE

FILE NAME = c:\pwork\puidot\stefenmk\d0121426\074052-shi-deta1.dgn	USER NAME = stefenmk	DESIGNED - 08-03-99	REVISED - 03-13-07
PLOT SCALE = 100.0000' / 1in.	CHECKED -	DATE -	REVISED -
PLOT DATE = 6/6/2014	DATE -		REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

RURAL ENTRANCE SCHEDULE AND MAILBOX TURNOUT DETAILS WITH SHOULDERS			
SCALE: NA	SHEET NO. 2 OF 2 SHEETS	STA. TO STA.	

F.A.S. RTE. 2801	SECTION 102RS-3.103RS-2.102N	COUNTY	TOTAL SHEETS 84	SHEET NO. 14
EFFINGHAM, FAYETTE		CONTRACT NO. 74052		
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				