

GUARDRAIL SCHEDULE

STATION TO STATION				STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 6B	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	GUARDRAIL REMOVAL	GUARDRAIL MARKER, TYPE A	TERMINAL MARKER - DIRECT APPLIED
				FT	EACH	EACH	FT	EACH	EACH
RT STA	339+57	TO	RT STA 342+76	212.5	1	1	313	5	1
LT STA	342+11	TO	LT STA 345+31	212.5	1	1	314	5	1
RT STA	351+93	TO	RT STA 354+43	150	-	2	250	4	2
LT STA	353+69	TO	LT STA 356+19	150	-	2	250	4	2
RT STA	394+78	TO	RT STA 397+28	150	-	2	253	4	2
LT STA	397+44	TO	LT STA 399+94	150	-	2	250	4	2
RT STA	424+51	TO	RT STA 427+70	212.5	1	1	312	5	1
LT STA	427+08	TO	LT STA 430+28	212.5	1	1	315	5	1
RT STA	450+60	TO	RT STA 456+23	462.5	-	2	555	8	2
LT STA	452+50	TO	LT STA 454+38	87.5	-	2	186	4	2
LT STA	457+44	TO	LT STA 459+57	112.5	-	2	211	4	2
TOTALS:				2113	4	18	3209	53	18

RESURFACING SCHEDULE

STATION TO STATION			LENGTH	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	HOT-MIX ASPHALT SURFACE REMOVAL, 5'	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HMA BINDER COURSE, IL-19.0 FC, N90	POLYMERIZED HMA BINDER COURSE, IL-19.0 FG, N90	POLYMERIZED HMA SURFACE COURSE, MIX "D", N90	HMA SHOULDERS	MATERIAL TRANSFER DEVICE	SHOULDER RUMBLE STRIPS, 16 INCH	AGGREGATE WEDGE SHOULDER, TYPE B
			FOOT	SQ YD	SQ YD	SQ YD	POUND	TON	TON	TON	TON	TON	TON	TON	FOOT
286+89	TO	427+39	14050	44076	1422	73867	87555	539	9253	9345	6272	3700	24870	55100	889
427+39	TO	481+59	5420	17116	0	28907	33718	208	3642	3642	2428	1438	9713	21680	343
TOTALS:			19470	61192	1422	102774	121273	747	12895	12987	8700	5138	34583	76780	1232

PAVEMENT MARKING SCHEDULE

STATION TO STATION			LENGTH	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID-LINE-6"	GROOVING FOR RECESSED PAVEMENT MARKING 5"	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 6"	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	DELINEATORS
			FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	SQ FT	EACH	EACH
286+89	TO	427+39	14050	56200	7025	56200	56200	7025	15736	1686	22246	703	70
427+39	TO	481+59	5420	21680	2710	21680	21680	2710	6070	650	8582	271	54
TOTALS:			19470	77880	9735	77880	77880	9735	21806	2336	30828	974	124