

REMOVAL SCHEDULE

STATION TO STATION	LENGTH FOOT	PAVED SHOULDER REMOVAL SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL, 6" SQ YD	PAVEMENT REMOVAL SQ YD	EARTH EXCAVATION (SPECIAL) CU YD	HOT-MIX ASPHALT SURFACE REMOVAL, 2" SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL, 3" SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL, 4" SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT SQ YD
EB I-70											
1036+00.00 TO 1043+44.00	744.0	661.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1043+44.00 TO 1045+19.00	175.0	155.6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	288.9
1045+19.00 TO 1056+45.00	1126.0	1000.9	3002.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1056+45.00 TO 1057+45.00	100.0	88.9	266.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1057+45.00 TO 1068+15.00	1070.0	951.1	2853.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1068+15.00 TO 1077+95.00	980.0	871.1	0.0	2613.3	1179.6	1088.9	0.0	0.0	0.0	0.0	0.0
1077+95.00 TO 1086+30.00	835.0	742.2	2226.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1086+30.00 TO 1087+30.00	100.0	88.9	266.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1087+30.00 TO 1100+60.00	1330.0	1182.2	3546.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1100+60.00 TO 1101+60.00	100.0	88.9	266.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1101+60.00 TO 1124+80.00	2320.0	2062.2	6186.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1124+78.00 TO 1131+51.00	673.0	598.2	2618.4	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1131+51.00 TO 1138+90.00	739.0	656.9	1970.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1138+90.00 TO 1148+70.00	980.0	871.1	0.0	2613.3	1324.8	0.0	0.0	1088.9	0.0	0.0	0.0
1148+70.00 TO 1152+32.00	362.0	321.8	965.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1152+32.00 TO 1153+50.00	118.0	104.9	314.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1153+50.00 TO 1154+50.00	100.0	88.9	451.8	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1154+50.00 TO 1163+19.00	869.0	772.4	3240.6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1163+19.00 TO 1167+85.00	466.0	414.2	1242.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1167+85.00 TO 1169+40.00	155.0	137.8	413.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1169+40.00 TO 1170+70.00	130.0	115.6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	288.9
1170+70.00 TO 1173+20.00	250.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1173+20.00 TO 1174+50.00	130.0	115.6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	288.9
1174+50.00 TO 1176+05.00	155.0	137.8	413.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1176+05.00 TO 1217+20.00	4115.0	3657.8	10973.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1217+20.00 TO 1218+20.00	100.0	88.9	266.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1218+20.00 TO 1237+65.00	1945.0	1728.9	5186.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1237+65.00 TO 1247+45.00	980.0	871.1	0.0	2613.3	1179.6	1088.9	0.0	0.0	0.0	0.0	0.0
1247+45.00 TO 1269+70.00	2225.0	1977.8	5933.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1269+70.00 TO 1270+70.00	100.0	88.9	266.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1270+70.00 TO 1278+05.00	735.0	653.3	1960.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

△ REVISED SHEET 7-21-14

EFFINGHAM & FAYETTE

FILE NAME: c:\pwwork\p\dos\stef\enmk\03180677\074469\sh\rsch.dgn	USER NAME: stef/enmk	DESIGNED: -	REVISED: -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.I. RTE.:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE: 1/8" = 100.000' / 1" = 1000.000'	CHECKED: -	REVISED: -		70	(26-5,26-5-1,25-1-1R)	-	92	18			
	PLOT DATE: 7/16/2014	DATE: -	REVISED: -		SCALE: NA	SHEET NO. 4 OF 16 SHEETS	STA. TO STA.	CONTRACT NO. 74469				
								ILLINOIS FED. AID PROJECT				