RESURFACING SCHEDULE (CONTINUED)

STATION TO STATION	LENGTH	HOT-MIX ASPHALT SHOULDERS, 13"	RUBBLIZING PORTLAND CEMENT CONCRETE PAVEMENT	TRIAXIAL GEOGRID REINFORCEMENT, TYPE I	SUBBASE GRANULAR MATERIAL (SPECIAL)	BITUMINOUS MATERIALS (PRIME COAT)	HOT-MIX ASPHALT BASE COURSE, 4 3/4"	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0 FG, N105	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	LEVELING BINDER (MACHINE METHOD), N90	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	HOT-MIX ASPHALT SHOULDERS	AGGREGATE WEDGE SHOULDER, TYPE B	SHOULDER RUMBLE STRIPS, 16 INCH	TEMPORARY RAMP	MATERIAL TRANSFER DEVICE
	FOOT	SQ YD	SQ YD	SQ YD	CU YD	POUND	SQ YD	TON	TON	TON	TON	TON	TON	TON	FOOT	SQ YD	TON
EB I-70 (CONTINUED)																	
1278+05.00 TO 1279+05.00	100.0	111.1	0.0	0.0	0.0	420.0	0.0	106.8	37.5	34.7	0.0	0.0	33.0	28.8	200.0	0.0	72.2
1279+05.00 TO 1285+05.00	600.0	666.7	1600.0	0.0	0.0	2160.0	0.0	640.6	225.2	208.0	0.0	0.0	197.9	172.7	1200.0	0.0	433.2
1285+05.00 TO 1286+86.00	181.0	201.1	0.0	0.0	0.0	760.2	0.0	193.3	67.9	62.7	0.0	0.0	59.7	52.1	362.0	0.0	130.6
1286+86.00 TO 1294+95.00	809.0	898.9	2157.3	0.0	0.0	2912.4	0.0	863.8	303.7	280.5	0.0	0.0	266.8	232.9	1618.0	0.0	584.2
1294+95.00 TO 1300+02.98	508.0	564.4	0.0	1354.6	602.1	1930.3	1354.6	531.0	189.6	176.1	0.0	0.0	101.1	19.3	1016.0	0.0	365.7
1300+02.98 TO 1304+75.00	472.0	524.5	0.0	1258.7	559.4	1793.7	1258.7	493.4	176.2	163.6	0.0	0.0	94.0	17.9	944.0	0.0	339.8
1304+75.00 TO 1314+50.00	975.0	1083.3	2600.0	0.0	0.0	3510.0	0.0	1041.0	366.0	338.0	0.0	0.0	321.5	280.7	1950.0	0.0	704.0
1314+50.00 TO 1315+50.00	100.0	111.1	0.0	0.0	0.0	420.0	0.0	106.8	37.5	34.7	0.0	0.0	33.0	28.8	200.0	0.0	72.2
1315+50.00 TO 1361+00.00	4550.0	5055.6	12133.3	0.0	0.0	16380.0	0.0	4858.1	1708.0	1577.3	0.0	0.0	1529.4	1309.9	9100.0	0.0	3285.3
1361+00.00 TO 1362+00.00	100.0	111.1	0.0	0.0	0.0	420.0	0.0	106.8	37.5	34.7	0.0	0.0	33.0	28.8	200.0	0.0	72.2
1362+00.00 TO 1383+15.00	2115.0	2350.0	5640.0	0.0	0.0	7614.0	0.0	2258.2	793.9	733.2	0.0	0.0	697.5	608.9	4230.0	0.0	1527.1
1383+15.00 TO 1384+45.00	130.0	144.4	0.0	0.0	0.0	546.0	0.0	138.8	48.8	45.1	0.0	0.0	42.9	37.4	260.0	0.0	93.9
1384+45.00 TO 1399+50.00	1505.0	1672.2	4013.3	0.0	0.0	5418.0	0.0	1606.9	564.9	521.7	0.0	0.0	496.3	433.3	3010.0	0.0	1086.6
1399+50.00 TO 1400+50.00	100.0	111.1	0.0	0.0	0.0	420.0	0.0	106.8	37.5	34.7	0.0	0.0	33.0	28.8	200.0	0.0	72.2
1400+50.00 TO 1409+80.00	930.0	1033.3	2480.0	0.0	0.0	3348.0	0.0	993.0	349.1	322.4	0.0	0.0	306.7	267.7	1860.0	0.0	671.5
1409+85.00 TO 1410+85.00	100.0	111.1	0.0	0.0	0.0	420.0	0.0	106.8	37.5	34.7	0.0	0.0	33.0	28.8	200.0	0.0	72.2
1410+85.00 TO 1414+20.00	335.0	372.2	893.3	0.0	0.0	1206.0	0.0	357.7	125.8	116.1	0.0	0.0	110.5	96.4	670.0	0.0	241.9
1414+20.00 TO 1418+38.64	418.6	465.2	0.0	1116.4	496.2	1590.8	1116.4	437.6	156.3	145.1	0.0	0.0	83.4	15.9	837.3	0.0	301.4
1418+38.64 BK= 1418+38.81AH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1418+38.81 TO 1424+00.00	561.2	623.5	0.0	1496.5	665.1	2132.5	1496.5	586.6	209.5	194.5	0.0	0.0	111.7	21.3	1122.4	0.0	404.0
1424+00.00 TO 1436+50.00	1250.0	1388.9	3333.3	0.0	0.0	4500.0	0.0	1334.6	469.2	433.3	0.0	0.0	412.2	359.9	2500.0	0.0	902.5
1436+50.00 TO 1437+50.00	100.0	111.1	0.0	0.0	0.0	420.0	0.0	106.8	37.5	34.7	0.0	0.0	33.0	28.8	200.0	0.0	72.2
1437+50.00 TO 1449+50.00	1200.0	1333.3	3200.0	0.0	0.0	4320.0	0.0	1281.2	450.5	416.0	0.0	0.0	395.7	345.5	2400.0	0.0	866.5
1449+50.00 TO 1450+50.00	100.0	111.1	0.0	0.0	0.0	420.0	0.0	106.8	37.5	34.7	0.0	0.0	33.0	28.8	200.0	0.0	72.2
1450+50.00 TO 1461+85.00	1135.0	1261.1	3026.7	0.0	0.0	4086.0	0.0	1211.8	426.1	393.5	0.0	0.0	374.3	326.8	2270.0	0.0	819.6
1461+85.00 TO 1462+63.50	78.5	87.2	0.0	0.0	0.0	329.7	0.0	45.5	45.5	27.2	0.0	0.0	25.9	22.6	157.0	0.0	72.7
1462+63.50 BK= 1521+78.59AH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1521+78.59 TO 1522+55.00	76.4	84.9	0.0	0.0	0.0	320.9	0.0	44.2	44.2	26.5	0.0	0.0	25.2	22.0	152.8	0.0	70.7
1522+55.00 TO 1523+85.00	130.0	144.4	0.0	0.0	0.0	546.0	0.0	7.4	24.4	45.1	0.0	0.0	34.4	37.4	260.0	66.7	69.5
EB I-70 TOTALS		47351.9	91552.0	13066.2	5807.2	153060.1	13066.2	44581.8	15895.7	14767.2	0.0	0.0	13218.6	10841.1	83473.5	266.7	30662.9

1 REVISED SHEET 7-21-14

• EFFINGHAM & FAYETTE

FILE NAME - c:\pw_work\pwidot\steffenmk\d0186577\D774469-sht-scn.dgn	USER NAME = steffenmk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.I. RTE. 70	SECTION (26-5,26-5-1,25-1-1)R	COUNTY •	TOTAL SHEETS 92	SHEET NO. 24
		DRAWN -	REVISED -					CONTRACT NO. 74469		
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -		SCALE: NA / SHEET NO. 10 OF 16 SHEETS / STA. TO STA.		ILLINOIS FED. AID PROJECT			
	PLOT DATE = 7/16/2014	DATE -	REVISED -							