

SUMMARY OF QUANTITIES				100% STATE CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	FAYETTE COUNTY 0004	EFFINGHAM COUNTY 0004	FAYETTE S.N. 026-0055 0014
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	178514	112576	65938	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	21070	12820	8250	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2573	2573		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	5284	3304	1980	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	12487.5	8350	3587.5	550
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	12487.5	8350	3587.5	550
70600240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2			2
70600251	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	10	6	4	
70600340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2			2
70600352	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	10	6	4	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	178514	112576	65938	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2573	2573		

SUMMARY OF QUANTITIES				100% STATE CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	FAYETTE COUNTY 0004	EFFINGHAM COUNTY 0004	FAYETTE S.N. 026-0055 0014
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	21070	12820	8250	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2772	1948	824	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	129	74	51	4
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	39	20	15	4
78300100	PAVEMENT MARKING REMOVAL	SO FT	28096	17106	10990	
* D2002972	EVERGREEN, PINUS STROBUS (EASTERN WHITE PINE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	52	26	26	
X0322278	RODENT SHIELDS	EACH	431	267	164	
X0325279	CLASS SI CONCRETE (MISCELLANEOUS)	CU YD	647	401	246	
X0327487	TRIAxIAL GEOGRID REINFORCEMENT, TYPE I	SO YD	50045	42209	7836	
X2020410	EARTH EXCAVATION (SPECIAL)	CU YD	24495	20778	3717	
X3112900	SUBBASE GRANULAR MATERIAL (SPECIAL)	CU YD	22243	18760	3483	
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	320149	199717	120432	

* SPECIALTY ITEM

• EFFINGHAM & FAYETTE

FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
en:\pwork\pwidth\ever\tr\id\186577\077469-shs-eaq.dgn		DRAWN -	REVISED -		TO	(26-5,26-5-1,25-1-1)R		92	7			
PLOT SCALE = 1/8"=1'-0"		CHECKED -	REVISED -		SCALE: NA SHEET NO. 4 OF 5 SHEETS STA. TO STA.			ILLINOIS FED. AID PROJECT				
PLOT DATE = 6/5/2014		DATE -	REVISED -					CONTRACT NO. 74469				