UNDERDRAIN SCHEDULE (Cont'd)

STATIONS ARE ALONG CENTERLINE UNLESS NOTED OTHERWISE

DRAIN SLOPE IS 0.4% OR PGL

FROM STATION	TO STATION	PVT SLOPE (%)	DRAIN SLOPE (%)	PIPE UNDERDRAINS, 6" EASTBOUND OUTSIDE (FT)	PIPE UNDERDRAINS, 6" EASTBOUND INSIDE (FT)	PIPE UNDERDRAINS, 6" WESTBOUND OUTSIDE (FT)	PIPE UNDERDRAINS, 6" WESTBOUND INSIDE (FT)	PIPE UNDERDRAINS, 6" (SPECIAL) EASTBOUND OUTSIDE (FT)	%	EASTBOUND INSIDE (FT)	%	WESTBOUND OUTSIDE (FT)	%	WESTBOUND INSIDE (FT)	%	CLASS SI CONCRETE (MISC) (CU. YD.)	REINFORCEMENT BARS (LBS)	RODENT SHIELDS (EACH)	HMA SHOULDER REMOVAL & REPLACEMENT, 8" (FOR UNDERDRAIN TRENCH) EASTBOUND OUTSIDE (FT)	EASTBOUND INSIDE (FT)	WESTBOUND OUTSIDE (FT)	WESTBOUND INSIDE (FT)	HMA SHOULDER REMOVAL & REPLACEMENT, 8" (FOR UNDERDRAIN (SPCL) TRENCH) EASTBOUND OUTSIDE (FT)	EASTBOUND INSIDE (FT)	WESTBOUND OUTSIDE (FT)	WESTBOUND INSIDE (FT)
1313+00.00	1318+00.00	+0.2	0.4	500.0	500.0	500.0	500.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	500.0	500.0	500.0	500.0	10.0	4.0	10.0	4.0
1318+00.00	1323+00.00	+0.2	0.4	500.0	500.0	500.0	500.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	500.0	500.0	500.0	500.0	10.0	4.0	10.0	4.0
1323+00.00	1328+00.00	+0.2	0.4	500.0	500.0	500.0	500.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	500.0	500.0	500.0	500.0	10.0	4.0	10.0	4.0
1328+00.00	1333+00.00	+0.2	0.4	500.0	500.0	500.0	500.0	0.0		0.0		0.0		0.0		0.0	0.0	0.0	500.0	500.0	500.0	500.0	0.0	0.0	0.0	0.0
1333+00.00	1338+00.00	-0.697	PGL	500.0	500.0	500.0	500.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	500.0	500.0	500.0	500.0	10.0	4.0	10.0	4.0
1338+00.00	1343+00.00	-0.697	PGL	500.0	500.0	500.0	500.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	500.0	500.0	500.0	500.0	10.0	4.0	10.0	4.0
1343+00.00	1348+00.00	-0.182	0.4	500.0	500.0	500.0	500.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	500.0	500.0	500.0	500.0	10.0	4.0	10.0	4.0
1348+00.00	1353+00.00	-0.182	0.4	500.0	500.0	500.0	500.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	500.0	500.0	500.0	500.0	10.0	4.0	10.0	4.0
1353+00.00	1358+00.00	-0.182	0.4	500.0	500.0	500.0	500.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	500.0	500.0	500.0	500.0	10.0	4.0	10.0	4.0
1358+00.00	1363+00.00	-0.406	PGL	500.0	500.0	500.0	500.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	500.0	500.0	500.0	500.0	10.0	4.0	10.0	4.0
1363+00.00	1368+00.00	-0.406	PGL	500.0	500.0	500.0	500.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	500.0	500.0	500.0	500.0	10.0	4.0	10.0	4.0
1368+00.00	1373+00.00	-0.406	PGL	500.0	500.0	500.0	500.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	500.0	500.0	500.0	500.0	10.0	4.0	10.0	4.0
1373+00.00	1378+00.00	-0.406	PGL	500.0	500.0	500.0	500.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	500.0	500.0	500.0	500.0	10.0	4.0	10.0	4.0
1378+00.00	1383+00.00	-0.406	PGL	500.0	500.0	500.0	500.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	500.0	500.0	500.0	500.0	10.0	4.0	10.0	4.0
1383+00.00	1384+50.00	-0.406	PGL	150.0	150.0	150.0	150.0	46.0	2.0	40.0	2.0	46.0	2.0	40.0	2.0	6.0	142.4	4.0	150.0	150.0	150.0	150.0	10.0	4.0	10.0	4.0
1384+50.00	1386+00.00	+0.232	0.4	150.0	150.0	150.0	150.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	150.0	150.0	150.0	150.0	10.0	4.0	10.0	4.0
1386+00.00	1391+00.00	+0.232	0.4	500.0	500.0	500.0	500.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	500.0	500.0	500.0	500.0	10.0	4.0	10.0	4.0
1391+00.00	1396+00.00	+0.232	0.4	500.0	500.0	500.0	500.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	500.0	500.0	500.0	500.0	10.0	4.0	10.0	4.0
1396+00.00	1401+00.00	+0.232	0.4	500.0	500.0	500.0	500.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	500.0	500.0	500.0	500.0	10.0	4.0	10.0	4.0
1401+00.00	1406+00.00	+0.232	0.4	500.0	500.0	500.0	500.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	500.0	500.0	500.0	500.0	10.0	4.0	10.0	4.0
1406+00.00	1411+00.00	+0.232	0.4	500.0	500.0	500.0	500.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	500.0	500.0	500.0	500.0	10.0	4.0	10.0	4.0
1411+00.00	1413+50.00	0.0	0.4	250.0	250.0	250.0	250.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	250.0	250.0	250.0	250.0	10.0	4.0	10.0	4.0
1413+50.00	1416+00.00	0.0	0.4	250.0	250.0	250.0	250.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	250.0	250.0	250.0	250.0	10.0	4.0	10.0	4.0
1416+00.00	1418+38.64	0.0	0.4	238.6	238.6	238.6	238.6	0.0		0.0		0.0		0.0		0.0	0.0	0.0	238.6	238.6	238.6	238.6	0.0	0.0	0.0	0.0
1418+38.64 BK =	1418+38.81 AH	STA EQUATION		0.0	0.0	0.0	0.0	0.0		0.0		0.0		0.0		0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1418+38.81	1418+50.00	0.0	0.4	11.2	11.2	11.2	11.2	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	11.2	11.2	11.2	11.2	10.0	4.0	10.0	4.0
1418+50.00	1421+00.00	0.0	0.4	250.0	250.0	250.0	250.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	250.0	250.0	250.0	250.0	10.0	4.0	10.0	4.0
1421+00.00	1423+50.00	0.0	0.4	250.0	250.0	250.0	250.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	250.0	250.0	250.0	250.0	10.0	4.0	10.0	4.0
1423+50.00	1426+00.00	0.0	0.4	250.0	250.0	250.0	250.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	250.0	250.0	250.0	250.0	10.0	4.0	10.0	4.0
1426+00.00	1428+50.00	0.0	0.4	250.0	250.0	250.0	250.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	250.0	250.0	250.0	250.0	10.0	4.0	10.0	4.0
1428+50.00	1431+00.00	0.0	0.4	250.0	250.0	250.0	250.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	250.0	250.0	250.0	250.0	10.0	4.0	10.0	4.0
1431+00.00	1433+50.00	0.0	0.4	250.0	250.0	250.0	250.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	250.0	250.0	250.0	250.0	10.0	4.0	10.0	4.0
1433+50.00	1436+00.00	0.0	0.4	250.0	250.0	250.0	250.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	250.0	250.0	250.0	250.0	10.0	4.0	10.0	4.0
1436+00.00	1438+50.00	0.0	0.4	250.0	250.0	250.0	250.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	250.0	250.0	250.0	250.0	10.0	4.0	10.0	4.0
1438+50.00	1441+00.00	0.0	0.4	250.0	250.0	250.0	250.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	250.0	250.0	250.0	250.0	10.0	4.0	10.0	4.0
1441+00.00	1443+50.00	0.0	0.4	250.0	250.0	250.0	250.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	250.0	250.0	250.0	250.0	10.0	4.0	10.0	4.0
1443+50.00	1446+00.00	0.0	0.4	250.0	250.0	250.0	250.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	250.0	250.0	250.0	250.0	10.0	4.0	10.0	4.0
1446+00.00	1448+50.00	0.0	0.4	250.0	250.0	250.0	250.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	250.0	250.0	250.0	250.0	10.0	4.0	10.0	4.0
1448+50.00	1451+00.00	0.0	0.4	250.0	250.0	250.0	250.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	250.0	250.0	250.0	250.0	10.0	4.0	10.0	4.0
1451+00.00	1456+00.00	+2.5	PGL	500.0	500.0	500.0	500.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	500.0	500.0	500.0	500.0	10.0	4.0	10.0	4.0
1456+00.00	1461+00.00	+2.5	PGL	500.0	500.0	500.0	500.0	23.0	2.0	20.0	2.0	23.0	2.0	20.0	2.0	6.0	142.4	4.0	500.0	500.0	500.0	500.0	10.0	4.0	10.0	4.0
1461+00.00	1462+63.50	+2.5	PGL	163.5	163.5	163.5	163.5	0.0		0.0		0.0		0.0		0.0	0.0	0.0	163.5	163.5	163.5	163.5	0.0	0.0	0.0	0.0
1462+63.50 BK =	1521+78.59 AH	STA EQUATION		0.0	0.0	0.0	0.0	0.0		0.0		0.0		0.0		0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1521+78.59	1523+80.00	+2.5	PGL	201.4	201.4	201.4	201.4	0.0		0.0		0.0		0.0		0.0	0.0	0.0	201.4	201.4	201.4	201.4	0.0	0.0	0.0	0.0
	SHEET TOTALS			15,164.7	15,164.7	15,164.7	15,164.7	897.0		780.0		897.0		780.0		228.0	5,411.2	152.0	15,164.7	15,164.7	15,164.7	15,164.7	380.0	152.0	380.0	152.0
	PROJECT TOTALS			41,428.7	41,828.7	41,111.7	41,828.7	2,530.0		2,260.0		2,553.0		2,260.0		646.5	15,343.6	431.0	41,428.7	41,828.7	41,111.7	41,828.7	1,070.0	432.0	1,080.0	432.0

• EFFINGHAM & FAYETTE

FILE NAME = c:\pw_work\pwidot\swartzrw\d0186577\D774469-sht-sch.dgn	USER NAME = swartzrw	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 6/5/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NA | SHEET NO. 3 OF 16 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	(26-5,26-5-1,25-1-1)R	•	92	17
		CONTRACT NO. 74469		
		ILLINOIS FED. AID PROJECT		