

PAVEMENT MARKING SCHEDULE

		WORK ZONE PAVEMENT MARKING REMOVAL	SHORT-TERM PAVEMENT MARKING				WORK ZONE PAVEMENT MARKING REMOVAL		THERMOPLASTIC PAVEMENT MARKING, 4 INCH	THERMOPLASTIC PAVEMENT MARKING, 8 INCH	THERMOPLASTIC PAVEMENT MARKING, 12 INCH	THERMOPLASTIC PAVEMENT MARKING, 24 INCH	GROOVING FOR RECESSED PAVEMENT MARKING, 5"	GROOVING FOR RECESSED PAVEMENT MARKING, 9"	GROOVING FOR RECESSED PAVEMENT MARKING, 13"	GROOVING FOR RECESSED PAVEMENT MARKING, 25"	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	RAISED REFLECTIVE PAVEMENT MARKER		DESCRIPTION
				EDGE LINE				EDGE LINE								CENTER LINE				
EASTBOUND		LENGTH	CENTERLINE	WHITE	YELLOW			WHITE	YELLOW							WHITE	CRYSTAL	AMBER		
STATION TO STATION		(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)	(SQ FT)	(FOOT)	(FOOT)							(FOOT)	(EACH)	(EACH)		
410+00.00	575+54.38	16554.38	1655.438	662	662	546	437	16554	16554			33109				4139	414			
80+00.00	119+00.00	3900.00	390	156	156	129	103	3900	3900			7800				975	98			
119+00.00	124+00.00	500.00	0	0	0	17	13	0	0			0				0	0		018-0046 STRUCTURE/RESURF. OMISSION	
124+00.00	138+50.00	1450.00	145	58	58	48	38	1450	1450			2900				363	36			
138+50.00	147+50.00	900.00	0	0	0	30	24	0	0			0				0	0		018-0048 STRUCTURE/RESURF. OMISSION	
147+50.00	153+75.00	625.00	62.5	25	25	21	17	625	625			1250				156	16			
153+75.00	166+00.00	1225.00	0	0	0	40	32	0	0			0				0	0		008-0050 STRUCTURE/RESURF. OMISSION	
166+00.00	185+47.00	1947.00	194.7	78	78	64	51	1947	1947			3894				487	49			
185+47.00	194+97.00	950.00	0	0	0	31	25	0	950			950				238	24		RAMP OMISSION	
194+97.00	213+25.00	1828.00	182.8	73	73	60	48	1828	1828			3656				457	46			
213+25.00	223+75.00	1050.00	0	0	0	35	28	0	1050			1050				263	26		RAMP OMISSION	
223+75.00	292+20.00	6845.00	684.5	274	274	226	181	6845	6845			13690				1711	171			
TOTAL		37774.38	3314.938	1326	1326	1247	997	33149	35149			68299				8787	879			
WESTBOUND		LENGTH	CENTERLINE	WHITE	YELLOW			WHITE	YELLOW							WHITE	CRYSTAL	AMBER		
STATION TO STATION		(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)	(SQ FT)	(FOOT)	(FOOT)							(FOOT)	(EACH)	(EACH)		
410+00.00	575+54.38	16554.38	1655.438	662	662	546	437	16554	16554			33109				4139	414			
80+00.00	118+00.00	3800.00	380	152	152	125	100	3800	3800			7600				950	95			
118+00.00	123+00.00	500.00	0	0	0	17	13	0	0			0				0	0		018-0045 STRUCTURE/RESURF. OMISSION	
123+00.00	139+25.00	1625.00	162.5	65	65	54	43	1625	1625			3250				406	41			
139+25.00	146+75.00	750.00	0	0	0	25	20	0	0			0				0	0		018-0047 STRUCTURE/RESURF. OMISSION	
146+75.00	152+75.00	600.00	60	24	24	20	16	600	600			1200				150	15			
152+75.00	165+50.00	1275.00	0	0	0	42	34	0	0			0				0	0		008-0049 STRUCTURE/RESURF. OMISSION	
165+50.00	186+88.00	2138.00	213.8	86	86	71	56	2138	2138			4276				535	53			
186+88.00	193+49.00	661.00	0	0	0	22	17	0	661			661				165	17		RAMP OMISSION	
193+49.00	216+32.00	2283.00	228.3	91	91	75	60	2283	2283			4566				571	57			
216+32.00	220+94.00	462.00	0	0	0	15	12	0	462			462				116	12		RAMP OMISSION	
220+94.00	292+20.00	7126.00	712.6	285	285	235	188	7126	7126			14252				1782	178			
TOTAL		37774.38	3412.638	1365	1365	1247	997	34126	35249			69376				8812	881			
RAMPS		LENGTH	CENTERLINE	WHITE	YELLOW			WHITE	YELLOW							WHITE	CRYSTAL	AMBER		
STATION TO STATION		(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)	(SQ FT)	(FOOT)	(FOOT)							(FOOT)	(EACH)	(EACH)		
188+52.32	200+00.00	1147.68						1148	1148	190	116	32	2295	190	116	32	56	13		NE RAMP A
200+00.00	214+15.51	1415.51						1416	1416				2831				32	16		NW RAMP B
389+15.00	400+52.00	1137.00						1137	1137	185	112	32	2274	185	112	32	73	11		SW RAMP C
400+00.00	413+66.62	1366.62						1367	1367				2733				96	21		SE RAMP D
TOTAL		5067	0	0	0	0	0	5067	5067	375	228	64	10134	375	228	64	0	257	61	
			6728	2691	2691	2493	1994	72343	75466	375	228	64	147808	375	228	64	17600	2017	61	
			12110		4488		147808										2078			