

90/10 FED/ST

CONSTR. CODE

URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY
				0004 URBAN
28001100	TEMPORARY EROSION CONTROL BLANKET	SQ YD	8450	8450
28100105	STONE RIPRAP, CLASS A3	SQ YD	22	22
28200200	FILTER FABRIC	SQ YD	22	22
31101810	SUBBASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	2444	2444
31101900	SUBBASE GRANULAR MATERIAL, TYPE C	TON	691	691
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	2549	2549
35501306	HOT-MIX ASPHALT BASE COURSE, 5 1/2"	SQ YD	1712	1712
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3.6	3.6
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	8668	8668
40600300	AGGREGATE (PRIME COAT)	TON	16.5	16.5
40600285	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	POUND	1943	1943
40600990	TEMPORARY RAMP	SQ YD	724	724
40603092	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 FG, N90	TON	1480	1480
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1363	1363
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	428	428
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	1903	1903

FILE NAME	USER NAME * USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.U. RITE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILES	PLOT SCALE * SCALE*	DRAWN -	REVISED -		9128	28-R-1	MADISON	64	5				
	PLOT DATE * DATE*	CHECKED -	REVISED -		SCALE: _____ SHEET 2 OF 6 SHEETS STA. _____ TO STA. _____				CONTRACT NO. 76F11				
		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								

114